# **50C**

**Fuses** 

**Fuseholders** 

Fuse clips

Protectors for all electronic circuits and equipment

# How to use this catalog

#### Example fuse requirements

Rated voltage:	DC 70 V or greater	Step 1
Terminal / mounting method:	Surface mount type	Step 2
Dimensions:	$^{W}2$ mm $\times$ $^{H}1.2$ mm $\times$ $^{L}4$ mm or less	Step 2
Characteristic:	Inrush-withstand	Step 3
Region of use:	North America	Step 4
Rated current (I <sub>N</sub> ):	1.25 A	Step 5

 $I_{\rm N}$  refers to the fuse's rated current (e.g., 1.1  $I_{\rm N}$  is 1.1 times the rated current).

Using the "Search by rated voltage" pages

- Step 1 Select a rated voltage for the fuse suitable for the circuit in which it is to be inserted. Only select fuses with DC rated voltage for DC circuits, and those with AC rated voltage for AC circuits. Select a rated voltage higher than the voltage of the circuit.
- Step 2 Select a fuse that meets your mounting and dimensional requirements.
- Step 3 Select the characteristic.
- Step 4 Select the certification mark according to the region of use.
- Step 5 Confirm the type name of the selected fuse and proceed to the indicated product specification page.

## Search by rated voltage (DC)

Step 1	Step 2	Step 3	Step 4					Step 5			
Rated voltage	Dimensions (mm)	Characteristic	PS *	(l) or <b>71</b>	or Or	(3)	\\$	Type name	Rated current	Page	
DC 72 V	<sup>w</sup> 1.6 × <sup>H</sup> 1.05 × <sup>L</sup> 3.2			•	•			11CF	100 mA-10 A	19	
		Quick-acting		•	•			11CFB	100 mA-10 A	18	
	BOC 72N 3.16A							P11CF	100 mA-10 A	22	
				•	•			11CT	100 mA-10 A	19	
		Inrush-withstand		•	•			11CTB	100 mA-10 A	18	
								P11CT	100 mA-10 A	22	


If you cannot find a fuse satisfying your requirements, please contact your SOC sales representative. This catalog does not include fuses that treat 130% of the rated current as a non-fusing current in order to protect equipment used domestically in Japan. Please contact a sales reresentative for these products.

## **IMPORTANT**

Before proceeding with final fuse selection, be sure to read Fuse Selection Process on p. 139 and Safety Precautions on p. 158.

The pre-arcing time-current characteristics on the individual product specification pages are plots of the average values of measurements obtained under conditions specified by us. These data are for reference only and are not intended to infer any guaranteed values.

## Product name composition



Certification combinations ( ● : Certification acquired)

Code	PS	<b>(1)</b> * / <b>(1)</b> *	(I) / <b>71</b> °	(2)	\$
N1	•	•	•	_	_
N2	•	_	•	_	_
N3	•	•	_	_	_
N4	•	•	•	•	_
N5	•	•	•	•	•
N6	_	•	•	•	•
N7	_	•	•	•	_

Please contact your sales representative for information on products with certification combinations not included in this catalog.

## RoHS-compliant

All products contained in this catalog are RoHS-compliant.

Products without the Pb-free indication use high melting temperature type solder containing 85% by weight or more lead. Application of lead in such solder is exempted from the RoHS Directive.

# Terminology / Abbreviations

11CT Type	Type name for products with the same size and dimensions as the 11CT. For example: 11CT, 11CF, P11CT, P11CF, DC35V11CT, DC35VP11CT, DC35VP11CF, DC86V11CT, 32V11CF, 11CFB, 11CTB
25CT Type	Type name for products with the same size and dimensions as the 25CT. For example: 25CT, 25CF, P25CT, P25CF, DC35VP25CF, DC35VP25CF, DC300V25CF
25RT Type	Type name for products with the same size and dimensions as the 25RT. For example: 25RT, 25RF, P25RT, P25RF, DC35VP25RT, DC35VP25RF

# Search by rated voltage (AC)

Rated voltag	e Dimensions (mm)	Characteristic	PS E	(I) or <b>91</b>	G or G	(3)	\$ Type name	Rated current	Page
AC 500 V	<sup>¢</sup> 6.35 × <sup>L</sup> 31.8	Inrush-withstand		•	•		SHV4	1 A–10 A	37
AC 500 V	<sup>⋄</sup> 5.2 × <sup>∟</sup> 20	Inrush-withstand		•	•		SHV12	100 mA-6.3 A	39
AC 500 V	<sup>φ</sup> 6.35 × <sup>L</sup> 31.8	Inrush-withstand		•	•		SHV33 NSHV3	10 A-30 A 1 A-10 A	43
AC 500 V	<sup>†</sup> 10 × <sup>L</sup> 32	_		•	•		500VBL1030A	5 A–50 A	54
AC 500 V	<sup>♦</sup> 10 × <sup>L</sup> 31	-		•	•		500VBI1030	5 A-50 A	54
AC 450 V	<sup>φ</sup> 10 × <sup>L</sup> 32	-					AC450VBL1030C	60 A	52
AC 400 V	<sup>¢</sup> 6.35 × <sup>L</sup> 31.8	Inrush-withstand		•	•	•	SHV14	10 A-20 A	40
(		mi usir-witi istai lu		•	•		O.17	1 A–20 A	40
AC 400 V	<sup>⋄</sup> 5.2 × <sup>L</sup> 20	Inrush-withstand		•	•	•	SHV12	1 A-6.3 A 100 mA-6.3 A	- 39

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltage	ge Dimensions (mm)	Characteristic	PS *	(I) or <b>71</b>	(#) or (#)	(3)	\	Type name	Rated current	Page
AC 400 V	<sup>#</sup> 6.35 × <sup>L</sup> 31.8	Inrush-withstand						NSHV13	5 A–25 A	44
		III don Wallotana						NSHV23A	1 A–20 A	47
AC 400 V	<sup>⋄</sup> 5.2 × <sup>L</sup> 20	Inrush-withstand		•	•			SHV11	100 mA-6.3 A	38
AC 380 V	<sup>¢</sup> 6.35 × <sup>L</sup> 31.8	Inrush-withstand		•	•			SHV4	Over 10 A–20 A	37
AC 380 V	<sup>\$\phi\$</sup> 5.2 × <sup>L</sup> 20	Inrush-withstand		•	•			SHV2	1 A-6.3 A	37
AC 380 V	<sup>∅</sup> 5.2 × <sup>L</sup> 20	Inrush-withstand		•	•			SHV1	1 A-6.3 A	36
AC 300 V	<sup>∅</sup> 6.35 × <sup>L</sup> 31.8	Inrush-withstand	•					SHV4	1 A-20 A	37
AC 300 V	<sup>∅</sup> 5.2 × <sup>L</sup> 20	Inrush-withstand	•					SHV2	1 A–6.3 A	37
AC 300 V	<sup>⋄</sup> 5.2 × <sup>L</sup> 20	Inrush-withstand	•					SHV1	1 A-6.3 A	36

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltag	e Dimensions (mm)	Characteristic	PS *	(l) or <b>71</b>	or (I)	(\$)	♡	Type name	Rated current	Page
AC 250 V	W3.6 × H3.6 × L17	Inrush-withstand	•	•	•	•		36CT	1 A-6.3 A	34
AC 250 V	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	Quick-acting		•	•			25CF	63 mA-4 A	24
		Inrush-withstand		•	•			25CT	100 mA-3.15 A	25
AC 250 V	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 9	Quick-acting		•	•			25RF	100 mA-10 A	28
AC 250 V	W4 × H7.7 × L8.4	Inrush-withstand	•	•	•	•		SMC N4	4 A	35
AC 250 V	<sup>φ</sup> 10.3 × <sup>∟</sup> 38.1	Normal-acting	•					250V (A) LLC	500 mA-30 A	124
			•					250V A TLLC	500 mA-30 A	129
	9 02		_	•	•			KST2	1 A-30 A	70
		Inrush-withstand	•	•	•			KST2 N1	6.3 A-30 A	70
_			•	•	•			SKM10	100 mA-30 A	90
	4				•			SKM10 N1	1 A-25 A	90
AC 250 V	<sup>φ</sup> 6.35 × <sup>L</sup> 31.8		•					250V (A) LNC	100 mA-20 A	123
		N. C.			•			SS2	50 mA-5 A	94
		Normal-acting		•	•			SS2 N1	50 mA-5 A	94
			•	•	•			SS6 SS6 N1	Over 5 A–8 A Over 5 A–8 A	95 97
								250V A TLNC	100 mA–20 A	128
6				•	•				100 mA-10 A	
Ģ	<u>**</u>			•				CES14	100 mA-15 A	67
		Inrush-withstand	•	•	•			CES14 N1	100 mA-10 A	67
				•				CES14 N2	Over 10 A-15 A	68
				•	•			ST4	100 mA-30 A	99
			•	•				ST4 N1	100 mA-8 A	99
AC 250 V	<sup>¢</sup> 6.35 × <sup>∟</sup> 30	Normal-acting	•					250V (A) LC	100 mA-20 A	122
(	\$ [ ] \$	Inrush-withstand	•					250V (A) TLC	100 mA-30 A	127
			•	•	•	•		TLC N4	8 A–25 A	106
AC 250 V	<sup>¢</sup> 6.35 × <sup>L</sup> 25.4	Normal-acting		•	•			SL4	80 mA-2 A	91

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltage	e Dimensions (mm)	Characteristic	PS *	(l) or <b>71</b>	or (F)	(3)	ኞ	Type name	Rated current	Page
AC 250 V	<sup>φ</sup> 5.2 × <sup>L</sup> 20					•		EQ	80 mA-6.3 A	57
		Quick-acting		•	•	•		HQ N7	400 mA-6.3 A	61
			•					250V (A) SC	100 mA-10 A	121
				•	•			1101	62 mA-3 A	
		Normal-acting		•				MQ4	62 mA-15 A	74
			•	•	•			MQ4 N1	62 mA-3 A	74
				•	•				100 mA-3.5 A	
				•				MT4	100 mA-15 A	80
				•	•			N4T4 D	100 mA-3.5 A	
				•				MT4 D	100 mA-15 A	82
		Inrush-withstand	•	•	•			MT4 N1	100 mA-3.5 A	80
			•	•	•			MT4 N1D	100 mA-3.5 A	83
			•	•				MT4 N2	Over 3.5 A-15 A	81
			•	•				MT4 N2D	Over 3.5 A-15 A	
			•					250V A TSC	100 mA-10 A	126
			•	•	•	•	•	ET	50 mA-6.3 A	58
		Time-lag	•	•	•	•		ET6	1 A-6.3 A	59
				•	•	•	•	HT N5	1 A-10 A	62
AC 250 V	<sup>φ</sup> 4.6 × <sup>L</sup> 16									
AO 230 V	4.0 × 10	Normal-acting	•					250V (A) MSC	100 mA-5 A	120
		Inrush-withstand	•					250V (A) TMSC	100 mA–5 A	125
AC 250 V	<sup>∅</sup> 10.3 × <sup>L</sup> 38.1	Normal-acting	•					250V A LLCR	500 mA-30 A	124
		Inrush-withstand	•					250V (A) TLLCR	500 mA-30 A	129
				•	•			SKM7	100 mA-30 A	89
AC 250 V	<sup>φ</sup> 6.35 × <sup>L</sup> 31.8							250V A LNCR	100 mA-20 A	123
				•	•			SS1	50 mA-5 A	93
		Normal-acting		•	•			SS1 N1	50 mA-5 A	93
Œ	S Pa			•	•			SS5	Over 5 A–8 A	95
=			•	•	•			SS5 N1	Over 5 A–8 A	96
			•					250V A TLNCR	100 mA-20 A	128
				•	•			CES15	100 mA-30 A	68
		Inrush-withstand	•	•	•			CES15 N1	100 mA-25 A	69
	11			•	•			ST3	100 mA-30 A	98
			•	•	•			ST3 N1	100 mA-8 A	98
AC 250 V	<sup>⋄</sup> 6.35 × <sup>∟</sup> 30	Normal-acting	•					250V (A) LCR	100 mA-20 A	122
	\ <u></u>	Inrush-withstand	•					250V (A) TLCR	100 mA-30 A	127
	Inrush-withsta	iii usii-witiistallu	•	•	•	•		TLCR N4	8 A–25 A	107
AC 250 V	<sup>6</sup> 6.35 × <sup>L</sup> 20	Inrush-withstand	•	•	•			250VTMCR N1	1 A–20 A	64

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltage	Dimensions (mm)	Characteristic	PS *	(I) Or <b>R1</b>	or OF	(3)	\$ Type name	Rated current	Page
AC 250 V	<sup>φ</sup> 5.2 × <sup>L</sup> 20		•				250V (A) SCR	100 mA-10 A	121
		NI		•	•			62 mA-3 A	
		Normal-acting		•			MQ3	62 mA-15 A	73
			•		•		MQ3 N1	62 mA-3 A	73
					•		MT3	100 mA-3.5 A	75
				•			IVITO	100 mA-15 A	7.5
				•	•		MT3 D	100 mA-3.5 A	77
				•				100 mA-15 A	
		Inrush-withstand		•	•		MT3 N1	100 mA-3.5 A	75
			•	•	•		MT3 N1D	100 mA-3.5 A	78
			•	•			MT3 N2	Over 3.5 A-15 A	_
			•	•			MT3 N2D	Over 3.5 A–15 A	_
			•				250V A TSCR	100 mA-10 A	126
		Time-lag				•	ET6R	1 A-6.3 A	60
				•	•	•	HTR N5	1 A–10 A	63
AC 250 V	¢ 4.6 × <sup>L</sup> 16	Normal-acting	•				250V @ MSCR	100 mA-5 A	120
		Inrush-withstand	•				250V @ TMSCR	100 mA–5 A	125
AC 250 V	4C 250 V	Quick-acting		•	•		NQ3	62 mA-10 A	87
		Inrush-withstand		•	•		NT3	100 mA-10 A	88
AC 250 V	<sup>♦</sup> 10 × <sup>L</sup> 32	-	•	•	•		AC250VBL1030C	40 A–60 A	52
AC 125 V	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	Quick-acting		•	•		25CF	Over 4 A–15 A	24
	NOC NOC	Quion dolling	•	•	•		2001	Over 4 A–6.3 A	
		Inruch withotand	•	•	•		25CT	Over 3.15 A–5 A	
		Inrush-withstand	•				2001	100 mA-5 A	25
AC 125 V		Quick-acting	•			•	25RF	200 mA-5 A	28
	sm.	Quick-acting	•				ZUNF	100 mA–5 A	20
		Inrush-withstand		•	•		25RT	100 mA-5 A	28

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltage Dimensions	s (mm) Characteristic	PS *	(I) or <b>R1</b>	or OF	(3)	\$ Type name	Rated current	Page
AC 125 V <sup>φ</sup> 10.3 × <sup>L</sup> 38	Normal-acting	•				(A) LLC	500 mA-30 A	114
8 4 4 4 4 A	Inrush-withstand	•				(A) TLLC	500 mA-30 A	119
	III usii-witiistant		•			SKM2	3 A–15 A	89
AC 125 V <sup>\$\phi\$</sup> 6.35 × \(^\mathbb{L}31	.8					(A) LNC	100 mA-20 A	113
	Normal-acting			•		SS6	Over 8 A-15 A	95
			•	•		SS6 N1	Over 8 A-15 A	97
		•				A TLNC	100 mA-20 A	118
8 4-4-1	<b>E</b>		•	•			100 mA-15 A	
						CES6	100 mA-20 A	65
	Inrush-withstand			•		CES6 N1	100 mA-15 A	65
				•		ST6	100 mA-30 A	102
				•		ST6 N1	100 mA-15 A	103
AC 125 V <sup>6</sup> 6.35 × L30	1	1				-		
AC 123 V 0.33 ^ 3C	Normal-acting	•				(A) LC	100 mA–20 A	112
	Inrush-withstand	•				(A) TLC	100 mA-30 A	117
AC 125 V	Normal-acting		•	•		SL2	80 mA–6 A	91
AC 125 V	Normal-acting		•			SU2	100 mA-20 A	104
AC 125 V <sup>\$\phi\$</sup> 5.2 × \(^\mathbb{L}20		•				(A) SC	100 mA-10 A	111
0.2 20				•			62 mA-10 A	
	Normal-acting		1	•		MQ2	62 mA-15 A	72
	-77			•		MQ2 N1	62 mA-10 A	72
3		•				⊕ TSC	100 mA–10 A	116
	Inrush-withstand	_				ULTSC	100 mA-10 A	108
	masii waliotan	1	•	•		ULTSC N1	100 mA–10 A	108
AC 125 V * 4.6 × L16	Normal-acting	•				(A) MSC	100 mA-5 A	110
	Inrush-withstand	•				(A) TMSC	100 mA-5 A	115

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltage Dimensions (mm)	Characteristic	PS E	(l) or <b>91</b>	Or OF	(\$)	\$ Type name	Rated current	Page
AC 125 V	Normal-acting		•	•		SQ8	80 mA-3 A	92
	Inrush-withstand		•	•		MT8	100 mA-3 A	85
AC 125 V	Normal-acting	•				(A) LLCR	500 mA-30 A	114
	Inrush-withstand	•				(A) TLLCR	500 mA-30 A	119
AC 125 V <sup>φ</sup> 6.35 × <sup>L</sup> 31.8		•				(A) LNCR	100 mA-20 A	113
	Normal-acting		•	•		SS5	Over 8 A-15 A	95
		•	•	•		SS5 N1	Over 8 A-15 A	96
		•				(A) TLNCR	100 mA-20 A	118
			•	•		CES7	100 mA-15 A	66
	Inrush-withstand	•	•	•		CES7 N1	100 mA-15 A	66
11			•	•		ST5	100 mA-30 A	100
		•	•	•		ST5 N1	100 mA-15 A	101
© 125 V	Normal-acting	•				@ LCR	100 mA-20 A	112
	Inrush-withstand	•				(A) TLCR	100 mA-30 A	117
AC 125 V	Normal-acting		•			SU1	80 mA–5 A	104
AC 125 V		•				(A) SCR	100 mA-10 A	111
		_	•	•			62 mA-10 A	
	Normal-acting			•		MQ1	62 mA-15 A	71
		•	•	•		MQ1 N1	62 mA-10 A	71
		•				(A) TSCR	100 mA-10 A	116
	Inrush-withstand		•	•		ULTSCR	100 mA-10 A	109
a. II.		•	•	•		ULTSCR N1	100 mA-10 A	109
AC 125 V	Normal-acting	•				(A) MSCR	100 mA-5 A	110
	Inrush-withstand	•				(A) TMSCR	100 mA–5 A	115
AC 125 V * 4.6 × L14	Normal-acting		•	•		SQ7	80 mA-3 A	92
	Inrush-withstand		•	•		MT7	100 mA-3 A	85

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltag	e Dimensions (mm)	Characteristic	PS *	(l) or <b>71</b>	or (F)	(3)	\$ Type name	Rated current	Page
AC 125 V	<sup>⋄</sup> 4× <sup>L</sup> 9	Quick-acting		•	•		NQ1	62 mA-10 A	87
		Inrush-withstand		•	•		NT1	100 mA-10 A	88
AC 90 V	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 9	Quick-acting					P25RF	100 mA-10 A	29
	977	Inrush-withstand					P25RT	100 mA-6.3 A	29
AC 42 V	<sup>⋄</sup> 5.2 × <sup>L</sup> 20	Inrush-withstand					PMT4	100 mA-20 A	86
AC 32 V	W 1.6 × H1.05 × L3.2	Inrush-withstand				•	32V11CF	800 mA-6.3 A	21
AC 32 V	<sup>W</sup> 1.5 × <sup>H</sup> 1.2 × <sup>L</sup> 2.4	Quick-acting		•	•		MCF3	28 mA-250 mA	31
AC 25 V	W 1.5 × H1.2 × L2.4	Quick-acting		•	•		MCF3	260 mA-1 A	31
AC 12.5 V	W 1.5 × H1.2 × L2.4	Quick-acting		•	•		MCF3	1.1 A–2.5 A	31

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

# Search by rated voltage (DC)

Rated voltage Dimensions (n	nm) Characteristic	PS *	(I) or <b>71</b>	or (I)	(3)	₩	Type name	Rated current	Page
DC 800 V	-						PT4065	400A	56
DC 700 V	Inrush-withstand	d	•	•			SHV16	1 A-4 A	41
DC 700 V	Inrush-withstand	d					NSHV15	1 A-4 A	46
DC 600 V W3.6 × H3.6 × L	Quick-acting		•	•			36CFA	63 mA-3.15 A	35
DC 600 V	Normal-acting						LLD6500	15 A	105
DC 600 V	_						DC600VBI625C	30 A	51
DC 550 V	_						DC550VBI625C	35 A	50
DC 500 V	-						PT4065	400 A–500 A	56
DC 500 V	Inrush-withstand	d	•	•			SHV22	1 A-10 A	42

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltag	e Dimensions (mm)	Characteristic	PS *	(I) or <b>71</b>	(1) or (1)	(3)	\$ Type name	Rated current	Page
DC 500 V	<sup>¢</sup> 6.35 × <sup>L</sup> 31.8	Inrush-withstand					NSHV14	10 A	46
DC 500 V	<sup>⋄</sup> 6.35 × <sup>L</sup> 25.4	Inrush-withstand		•	•		SHV18	1 A–30 A	41
DC 500 V	<sup>¢</sup> 6.35 × <sup>L</sup> 25.4	Inrush-withstand					NSHV17	1 A-30 A	47
DC 500 V	<sup>ф</sup> 25 × <sup>L</sup> 42.6	-					DC500VBT2543	225 A	55
DC 500 V	<sup>φ</sup> 10 × <sup>L</sup> 32	_		•	•		500VBL1030A	5 A–50 A 5 A–40 A	- 54
							DC500VBL1030F	60 A	53
DC 500 V	<sup>¢</sup> 6.35 × <sup>L</sup> 31.8	-					DC500VBC635C	5 A-30 A	51
DC 500 V	<sup>⋄</sup> 6.35 × <sup>L</sup> 24.6	-					DC500VBC625A	5 A-35 A	49
DC 500 V	<sup>♦</sup> 10 × <sup>L</sup> 31	-		•	•		500VBI1030	5 A-50 A 5 A-40 A	- 54

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltage	Dimensions (mm)	Characteristic	PS *	(I) or <b>71</b>	or OF	(3)	\$ Type name	Rated current	Page
DC 500 V	<sup>¢</sup> 6.35 × <sup>L</sup> 24.6	-					DC500VBI625C	5 A-35 A	50
DC 450 V	<sup>⋄</sup> 5.2 × <sup>L</sup> 20	Inrush-withstand		•	•		SHV20	500 mA-6.3 A	42
							NSHV12	100 mA-6.3 A	45
DC 450 V	<sup>¢</sup> 6.35 × <sup>L</sup> 25.4	Inrush-withstand		•	•		SHV27	6.3 A	43
DC 450 V	<sup>ф</sup> 31 × <sup>L</sup> 51	-					DC450VPT3050	250 A-350 A	49
DC 450 V	<sup>♦</sup> 30 × <sup>L</sup> 50	_					DC450VBT3050	250 A-350 A	56
DC 450 V	* 26 × <sup>L</sup> 46	-					DC450VPT2545	180 A–225 A	48
DC 450 V	* 20 × <sup>L</sup> 35	-					DC450VPT2035	100 A-150 A	48
DC 425 V	<sup>₩</sup> 3.6 × <sup>H</sup> 3.6 × <sup>L</sup> 11	Quick-acting		•	•		36CFA	4 A	35
DC 420 V	<sup>∅</sup> 6.35 × <sup>L</sup> 25.4	Inrush-withstand		•	•		SHV27	8 A-30 A	43

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltag	ge Dimensions (mm)	Characteristic	PS E	(l) or <b>71</b>	or <b>(II</b> )	(3)	ኞ	Type name	Rated current	Page
DC 400 V	<sup>¢</sup> 6.35 × <sup>L</sup> 31.8			•	•	•			10 A-20 A	
		Inrush-withstand		•	•			SHV14	1 A-20 A	40
DC 400 V	<sup>φ</sup> 5.2 × <sup>L</sup> 20			•	•	•			1 A-6.3 A	
		Inrush-withstand		•	•			SHV12	100 mA-6.3 A	39
DC 400 V	<sup>φ</sup> 6.35 × <sup>L</sup> 31.8							NSHV13	5 A-25 A	44
		Inrush-withstand						NSHV23A	1 A–20 A	47
DC 400 V	<sup>⋄</sup> 5.2 × <sup>L</sup> 20	Inrush-withstand		•	•			SHV11	100 mA-6.3 A	38
DC 300 V	W3.6 × H3.6 × L17	Inrush-withstand		•	•			36CT	1 A-6.3 A	34
DC 300 V	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	Quick-acting		•	•			DC300V25CF	63 mA–2 A	25
DC 300 V	<sup>♦</sup> 6.35 × <sup>L</sup> 24.6	-						DC550VBI625C	35 A	50
DC 250 V	<sup>⋄</sup> 5.2 × <sup>∟</sup> 20	Inrush-withstand		•	•			SHV12	100 mA-6.3 A	39
DC 150 V	<sup>W</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	Quick-acting		•	•			25CF	63 mA–15 A	24

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltag	Dimensions (mm)	Characteristic	PS *	(I) or <b>71</b>	or ©	(3)	♡	Type name	Rated current	Page
DC 125 V	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	Inrush-withstand		•	•			25CT	100 mA-5 A	25
DC 125 V	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 9	Quick-acting		•	•	•		25RF	100 mA-10 A 200 mA-5 A	28
		Inrush-withstand		•	•			25RT	100 mA-5 A	28
DC 125 V	<sup>¢</sup> 6.35 × <sup>L</sup> 31.8	Inrush-withstand		•	•			ST6	100 mA–30 A	102
(		III asii-witiistana		•	•			ST6 N1	100 mA–15 A	103
DC 125 V	<sup> </sup>			•				MT4 D	100 mA-15 A	82
	\$ 22000	Inrush-withstand		•				MT4 N1D	100 mA-3.5 A	83
				•				MT4 N2D	Over 3.5 A–15 A	84
DC 125 V	<sup>¢</sup> 6.35 × <sup>L</sup> 31.8	Inrush-withstand		•	•			ST5	Over 8 A–30 A	100
		mash walstand		•	•			ST5 N1	Over 8 A–15 A	101
DC 125 V	<sup>⋄</sup> 6.35 × <sup>L</sup> 30	Inrush-withstand		•	•			DC125VTLKR	800 mA-35 A	64
DC 125 V	<sup>¢</sup> 5.2 × <sup>∟</sup> 20			•				MT3 D	100 mA-15 A	77
		Inrush-withstand		•				MT3 N1D	100 mA-3.5 A	78
				•				MT3 N2D	Over 3.5 A–15 A	79
DC 100 V	*4 × L9	Inrush-withstand						PNT5	100 mA-10 A	86
DC 90 V	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 9	Quick-acting						P25RF	100 mA-10 A	29

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltage	Dimensions (mm)	Characteristic	PS *	or <b>91</b>	or OF	(3)	\$ Type name	Rated current	Page
DC 86 V	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	Quick-acting		•	•		25CF	63 mA–5 A	24
		Inrush-withstand		•	•		25CT	100 mA–5 A	25
DC 86 V	W1.6 × H1.05 × L3.2	Inrush-withstand		•	•		DC86V11CT	100 mA-8 A	20
DC 72 V	<sup>W</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	Quick-acting		•			25CF	18 A	24
DC 72 V	<sup>W</sup> 1.6 × <sup>H</sup> 1.05 × <sup>L</sup> 3.2			•	•		11CF	100 mA-10 A	19
		Quick-acting		•	•		11CFB	100 mA-10 A	18
	3.15A						P11CF	100 mA-10 A	22
				•	•		11CT	100 mA-10 A	19
		Inrush-withstand		•	•		11CTB P11CT	100 mA–10 A 100 mA–10 A	18 22
DC 72 V	<sup>W</sup> 1.5 × <sup>H</sup> 1.2 × <sup>L</sup> 2.4	Quick-acting		•	•		MCF3	28 mA–250 mA	31
DC 72 V	<sup>♦</sup> 10 × <sup>L</sup> 32	-					DC72VBL1030	50 A-70 A	53
DC 60 V	<sup>W</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	Quick-acting					P25CF	63 mA–18 A	26
		Inrush-withstand					P25CT	100 mA-5 A	26
DC 60 V		Inrush-withstand					P25RT	100 mA-6.3 A	29

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

Rated voltag	e Dimensions (mm)	Characteristic	PS *	(l) or <b>91</b>	(a) o (b)	(3)	\$ Type name	Rated current	Page
DC 60 V	<sup>¢</sup> 6.35 × <sup>L</sup> 15.9	Normal-acting		•			DCSU2	Over 5 A–20 A	105
DC 42 V	<sup>⋄</sup> 5.2 × <sup>∟</sup> 20	Inrush-withstand					РМТ4	100 mA-20 A	86
DC 35 V	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	Quick-acting					DC35VP25CF	63 mA–18 A	27
		Inrush-withstand					DC35VP25CT	100 mA–5 A	27
DC 35 V	<sup>w</sup> 1.6 × <sup>H</sup> 1.05 × <sup>L</sup> 3.2	Quick-acting					DC35VP11CF	100 mA-10 A	23
	T 3150	In words with a town		•			DC35V11CT	100 mA-10 A	20
		Inrush-withstand					DC35VP11CT	100 mA-10 A	23
DC 35 V	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 9	Quick-acting					DC35VP25RF	100 mA-10 A	30
		Inrush-withstand					DC35VP25RT	100 mA-6.3 A	30
DC 32 V	W1.6 × H1.05 × L3.2	Inrush-withstand		•	•	•	32V11CF	800 mA-6.3 A	21
DC 32 V	<sup>W</sup> 1.5 × <sup>H</sup> 1.2 × <sup>L</sup> 2.4	Quick-acting		•	•		MCF3	260 mA-1 A	31
DC 25 V	<sup>W</sup> 1.5 × <sup>H</sup> 1.2 × <sup>L</sup> 2.4	Quick-acting		•	•		MCF3	1.1 A–2.5 A	31

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.


Quick-acting

RoHS-compliant

Pb free

#### This product increases the 11CF's maximum usage temperature to 125 °C

Representative pre-arcing time-current characteristics



Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
DC 72 V	c <b>911</b> °us	100 mA–10 A	50 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 <i>I</i> <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

# 11CTB Inrush-withstand Rob


RoHS-compliant

Pb free

## This product increases the 11CT's maximum usage temperature to 125 $^{\circ}\text{C}$




- mmn	1.05
< 3.2 →	< 1.6



Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
DC 72 V	c <b>'91</b> 2°us	100 mA–10 A	50 A	Resistive circuit	75 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.



Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		Rated breaking current Temp. rise		Current carrying capacity	Overload operation
DC 72 V	<b>FL</b>	100 mA–10 A	50 A	Resistive circuit	75 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 <i>I</i> <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# **11CT**


Inrush-withstand

RoHS-compliant

Pb free








Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 72 V	<b>71</b>	100 mA–10 A	50 A	Resistive circuit	75 K or less at 1.0 / <sub>N</sub>	1.0 / <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.



Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 35 V	<b>71</b> °	100 mA-10 A	50 A	Resistive circuit	75 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 <i>I</i> <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

# DC86V11CT


Inrush-withstand

RoHS-compliant


Pb free















Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 86 V	c (UL) us	100 mA–8 A	50 A	Resistive circuit	75 K or less at 1.0 / <sub>N</sub>	1.0 / <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

#### Pre-arcing time-current characteristics




Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated breaking current		Temp. rise	Current carrying capacity / Endurance test	Overload operation
AC / DC 32 V	(2)	800 mA 2.5 A 3.15 A	50 A	Resistive	*2	*3	Within 2 min at 2.0 <i>I</i> <sub>N</sub> 0.001 s–0.01 s at 10 <i>I</i> <sub>N</sub>
DC 32 V	c <b>PL</b> °us	4 A 5 A 6.3 A	50 A	circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 / <sub>N</sub>

<sup>\*1:</sup> This fuse is categorized as "Inrush-withstand" within SOC; however, it is referred to as Type F (Quick-acting) in the certificate issued by SEMKO.

<sup>\*2:</sup> The temperature rise of the terminals is 70 K or less when measured during the last five minutes of carrying a 1.25 IN current for endurance testing.

 $<sup>^{\</sup>star}3$ : Endurance test: After 100 cycles of 1.05  $I_N$  1 h on / 15 min off, 1.25  $I_N$  is passed through the fuse for 1 h.



Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 72 V	-	100 mA-10 A	50 A	Resistive circuit	75 K or less at 1.0 / <sub>N</sub>	1.0 / <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Note: The rated current (in amperes) multiplied by 1,000 is indicated on the product and its packaging (e.g., "630" for the 0.63 A version). The product name is the type name followed by this value.

#### P11CT RoHS-compliant Protector Inrush-withstand Pb free Representative pre-arcing time-current characteristics 50C T 3150 passasal 1.05 1.6 3.2 1004 Land pattern for reflow soldering 5000 (reference dimensions) 3150 2000 1.8 1000 1.35 1.2 1.35 Scale: 8/1 (mm) Pre-arcing time


Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 72 V	-	100 mA-10 A	50 A	Resistive circuit	75 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

1.8

at 2.0 I<sub>N</sub>

#### Representative pre-arcing time-current characteristics



Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 35 V	-	100 mA-10 A	50 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Note: The rated current (in amperes) multiplied by 1,000 is indicated on the product and its packaging (e.g., "630" for the 0.63 A version). The product name is the type name followed by this value.

#### DC35VP11CT RoHS-compliant Protector Inrush-withstand Pb free Representative pre-arcing time-current characteristics 50C T 3150 7777 poooood 1.05 3.2 1.6 1004 Land pattern for reflow soldering 5000 (reference dimensions) 3150

2000

1000

	10ms 100		10s			K1.35 × 1.2 ×	Scale: 8/1 (mm)
е	Certification	Rated current (I <sub>N</sub> ) *1		n breaking rrent	Temp. rise	Current carrying capacity	Overload operation
	_	100 mA_10 A	50 A	Resistive	75 K or less	1.0 <i>I</i> <sub>N</sub> until temperature	Within 60 s

at 1.0 I<sub>N</sub>

stabilization

occurs

circuit

100 mA-10 A


Note: The rated current (in amperes) multiplied by 1,000 is indicated on the product and its packaging (e.g., "630" for the 0.63 A version). The product name is the type name followed by this value.

50 A

Maximum working voltage

DC 35 V

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.



Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		oreaking rent	Temp. rise	Current carrying capacity / Endurance test	Overload operation
AC 250 V	<b>FL</b>	63 mA–4 A			75 K or less	4.0 <i>l</i>	
	74 W	Over 4 A–10 A	50 A		at 1.0 I <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 <i>I</i> <sub>N</sub>
AC 125 V	<b>71</b> ° (1);	Over 10 A–15 A			100 K or less at 1.0 <i>I</i> <sub>N</sub>	occurs	
AC 123 V	PS *2	63 mA–6.3 A	*3	Resistive circuit	*4	*5	Within 2 min at 2.0 / <sub>N</sub> 0.001 s–0.01 s at 10 / <sub>N</sub>
DC 150 V	<b>71</b> ° (B°	63 mA–10 A	350 A		75 K or less at 1.0 <i>I</i> <sub>N</sub>		
DC 130 V	<b>71</b> ° (1);	Over 10 A–15 A	330 A		100 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 / <sub>N</sub> until temperature	Within 60 s
DC 86 V	<b>71 ®</b>	63 mA–5 A	10000 A		75 K or less	staḃilization occurs	at 2.0 / <sub>N</sub>
DC 72 V	<b>A</b> l <sup>®</sup>	18 A	100 A		at 1.0 / <sub>N</sub>		


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

<sup>\*3: 50</sup> A or 10 I<sub>N</sub>, whichever is greater.

<sup>\*4:</sup> The temperature rise of the terminals is 70 K or less when measured during the last five minutes of carrying a 1.25 IN current for endurance testing.

<sup>\*5:</sup> Endurance test: After 100 cycles of 1.05  $I_N$  1 h on / 15 min off, 1.25  $I_N$  is passed through the fuse for 1 h.



Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		oreaking rent	Temp. rise	Current carrying capacity/ Endurance test	Overload operation	
AC 250 V	c (UL) us	100 mA-3.15 A		50 A	75 K or less at 1.0 I <sub>N</sub>	1.0 I <sub>N</sub> until temperature	Within 60 s	
	0 1500	Over 3.15 A–5 A	50 A			stabilization occurs	at 2.0 / <sub>N</sub>	
AC 125 V	P\$ *2	100 mA–5 A	50 A	Resistive circuit	*3	*4	Within 2 min at 2.0 <i>I</i> <sub>N</sub>	
DC 125 V		100 MA-5 A	350 A		75 K or less	1.0 /N until temperature With	Within 60 s	
DC 86 V	c QL) us		10000 A		at 1.0 <i>I</i> <sub>N</sub>	stabilization occurs	at 2.0 I <sub>N</sub>	


- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- \*3: The temperature rise of the terminals is 70 K or less when measured during the last five minutes of carrying a 1.25 N current for endurance testing.
- \*4: Endurance test: After 100 cycles of 1.05 I<sub>N</sub> 1 h on / 15 min off, 1.25 I<sub>N</sub> is passed through the fuse for 1 h.

# DC300V25CF

Quick-acting

RoHS-compliant

Pb free



Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 300 V	c UL us	63 mA–2 A	50 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


Protector

Quick-acting

RoHS-compliant

Pb free

#### Representative pre-arcing time-current characteristics




Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
		63 mA-10 A		A Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 h. until	Within 60 s at 2.0 I <sub>N</sub>
DC 60 V	-	Over 10 A–15 A	50 A		100 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 / <sub>N</sub> until temperature stabilization	
		Over 15 A–18 A			75 K or less at 1.0 <i>I</i> <sub>N</sub>	occurs	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


Note: The rated current (in amperes) multiplied by 1,000 is indicated on the product and its packaging (e.g., "630" for the 0.63 A version). The product name is the type name followed by this value.

# P25CT Protector Inrush-withstand RoHS-compliant Pb free Representative pre-arcing time-current characteristics



Maximum working voltage	Certification	Rated current ( <i>I</i> <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 60 V	-	100 mA–5 A	50 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.



Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
		63 mA-10 A			75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 / <sub>N</sub> until	
DC 35 V	-	Over 10 A–15 A	50 A	Resistive circuit	100 K or less at 1.0 <i>I</i> <sub>N</sub>	temperature stabilization	Within 60 s at 2.0 <i>I</i> <sub>N</sub>
		Over 15 A–18 A			75 K or less at 1.0 <i>I</i> <sub>N</sub>	occurs	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Note: The rated current (in amperes) multiplied by 1,000 is indicated on the product and its packaging (e.g., "630" for the 0.63 A version). The product name is the type name followed by this value.

# DC35VP25CT


Protector

Inrush-withstand

RoHS-compliant


Pb free

#### Representative pre-arcing time-current characteristics




Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 35 V	-	100 mA–5 A	50 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.







Scale: 2/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation	Endurance test
AC 125 V	©	200 mA, 250 mA 315 mA, 400 mA 500 mA, 630 mA 800 mA, 1 A		PF over 0.95			*4	After passing
DC 125 V	(S)	1.25 A, 1.6 A 2 A, 2.5 A, 3.15 A 4 A, 5 A	50 A	Resistive circuit	*3	4 h or more at 1.0 I <sub>N</sub>	4	0.8 / <sub>N</sub> for 100 h, 1.0 / <sub>N</sub> can be passed for 1 h or more
AC 125 V	<b>PS</b> *2	100 mA-5 A *1		PF over 0.95			Within 5 s at 2.0 / <sub>N</sub>	
AC 250 V	c(UL) us	100 mA-10 A *1	100 A	Resistive	75 K or less	1.0 I <sub>N</sub> until temperature	Within 60 s	_
DC 125 V	U GL) US	100 mA=10 A *1		circuit	at 1.0 <i>I</i> <sub>N</sub>	staḃilization occurs	at 2.0 / <sub>N</sub>	_

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.
\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
\*3: After passing the rated current through the fuse for 15 min, the current is increased by 0.1 I<sub>N</sub> every 15 min until the fuse operates. While the current is being increased, the temperature rise at each part of the fuse shall not exceed 135 K

	moroacca, and temper	ataro noo at oaon par	cor and rade origin more	2X0000 100 1X.
*4:	2.0 I <sub>N</sub>	2.75 I <sub>N</sub>	4.0 I <sub>N</sub>	10 <i>I</i> N
	Within 5 s	Within 0.3 s	Within 0.03 s	Within 0.004 s


**25RT** 

Inrush-withstand


RoHS-compliant

Pb free

#### Representative pre-arcing time-current characteristics









Scale: 2/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	c UL us	100 mA–5 A	100 A	Resistive	75 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 I <sub>N</sub>
DC 125 V			300 A	circuit			

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.







Scale: 2/1 (mm)

Maximum working voltage	Certification	Rated current ( <i>I</i> <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 90 V DC 90 V	-	100 mA–10 A	50 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Note: The rated current (in amperes) multiplied by 1,000 is indicated on the product and its packaging (e.g., "630" for the 0.63 A version). The product name is the type name followed by this value.

# P25RT


Protector

Inrush-withstand


RoHS-compliant

Pb free

#### Representative pre-arcing time-current characteristics









Scale: 2/1 (mm)

Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 90 V DC 60 V	-	100 mA–6.3 A	50 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.







Scale: 2/1 (mm)

Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 35 V	-	100 mA-10 A	50 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Note: The rated current (in amperes) multiplied by 1,000 is indicated on the product and its packaging (e.g., "630" for the 0.63 A version). The product name is the type name followed by this value.

# DC35VP25RT


Protector

Inrush-withstand


RoHS-compliant

Pb free

#### Representative pre-arcing time-current characteristics








Scale: 2/1 (mm)

Maximum working voltage	Certification	Rated current ( <i>I</i> <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 35 V	-	100 mA-6.3 A	50 A	Resistive cirtcuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

## Airtight construction is achieved through use of highly precise insert molding techniques. \*2


Representative pre-arcing time-current characteristics







Land pattern for reflow soldering (reference dimensions)



Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 32 V		28 mA-250 mA	PF 0.95–1				
DC 72 V		28 MA-250 MA	260 mA–1 A 50 A -	Resistive circuit	75 K or less at 1.0 / <sub>N</sub>		
AC 25 V	<b>(</b>	260 4 4 4		PF 0.95–1		1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 s at 2.0 <i>I</i> <sub>N</sub>
DC 32 V	<b>շ (ՍԼ)</b> us	260 mA–1 A		Resistive circuit			
AC 12.5 V		110050		PF 0.95–1			
DC 25 V		1.1 A-2.5 A		Resistive circuit			


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


<sup>\*2:</sup> This product satisfies the requirements of IEC 60079-11 10.6.2.

Intentionally blank

Intentionally blank

(mm)





Rated voltage	Certification	Rated current (I <sub>N</sub> )		oreaking rent	Temp. rise	Current carrying capacity / Endurance test	Overload operation
	c <b>SN</b> °us	1A–6.3 A *1			75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>
AC 250 V	<u>S</u>	1 A 1.25 A 1.6 A 2 A 2.5 A 3.15 A 4 A 5 A 6.3 A	1500 A	PF 0.7–0.8	*2	*3	Within 2 min at 2.0 / <sub>N</sub> 0.01 s–0.1 s at 10 / <sub>N</sub>
	PS	1A-6.3 A *1	500 A		At 1.0 I <sub>N</sub> 140 K or less at the center, 60 K or less at the contact	1.0 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min
DC 300 V		IA-0.3 A	200 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.
\*2: The temperature rise of the terminals is 95 K or less when measured during the last five minutes of carrying a 1.25 I<sub>N</sub> current for endurance testing.

<sup>\*3:</sup> Endurance test: After 100 cycles of 1.05 I<sub>N</sub> 1 h on / 15 min off, 1.25 I<sub>N</sub> is passed through the fuse for 1 h.


4.25


4

Scale: 2/1

(mm)

#### Representative pre-arcing time-current characteristics





4.25

Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 600 V		63 mA-3.15 A *1	100 A	Resistive	75 K or less	1.0 / <sub>N</sub> until temperature	Within 60 s
DC 425 V	c <b>Flu</b> us	4 A	100 A	circuit	at 1.0 I <sub>N</sub>	staḃilization occurs	at 2.0 I <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


#### SMC N4 RoHS-compliant Inrush-withstand Pb free 8.4 Pre-arcing time-current characteristics SOC F 4A 250V 7.7 (S) (P) 100A φ0.6 19.5 5.08 Dimensions of mounting holes (for reference) $\phi 0.8$ Scale: 2/1 5.08 Pre-arcing time (mm)

	Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated breaking current		Temp. rise	Endurance test / Current carrying capacity	Pre-arcing time- current characteristics
	AC 250 V		4 A	40 A	PF over 0.95	*1	*2	*3
		c <b>FW</b> us		50 A		75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 30 min at 2.1 <i>I</i> <sub>N</sub>


<sup>\*1:</sup> After passing 1.5 I<sub>N</sub> through 15 min, the current is increased by 0.1 I<sub>N</sub> every 15 min until the fuse operates. While the current is being increased, the temperature rise at each part of the fuse shall not exceed 135 K.

\*2: After repeating 100 cycles of the rated current 1 h on / 15 min off, 1.5  $I_N$  is passed through the fuse for 1 h.

*3:	2.1 I <sub>N</sub>	2.75 I <sub>N</sub>	4.0 / <sub>N</sub>	10 <i>I</i> N
	Within 30 min	0.01 s-3 s	0.003 s-0.3 s	Within 0.02 s







φ 0.8


Lead wire diameter

Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 380 V	<b>71 (1)</b>	4.4.6.2.4	500 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 min
AC 300 V	PS E	1 A–6.3 A	500 A	PF 0.7–0.8	At 1.0 / <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.0 / <sub>N</sub> until constant temperature is obtained on each part	at 2.1 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 380 V	<b>71</b> 2 <b>(1)</b> 2	4 A C 2 A		Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 min
AC 300 V	PS E	1 A-6.3 A	500 A	PF 0.7–0.8	At 1.0 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.0 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 2.1 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# SHV4

Inrush-withstand


RoHS-compliant\*2

Pb free\*2

### Representative pre-arcing time-current characteristics







Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 500 V		1 A–10 A		Resistive	75 K or less	1.0 I <sub>N</sub> until temperature	
AC 380 V		Over 10 A–20 A	500 A	circuit	at 1.0 / <sub>N</sub>	staḃilization occurs	Within 60 min at 2.1 <i>I</i> <sub>N</sub>
AC 300 V	⟨PS⟩	1 A–20 A	500 A	PF 0.7–0.8	-	1.0 I <sub>N</sub> until constant temperature is obtained on each part	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


2: 1 A-6.3 A Pb free

Over 6.3 A-20 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Lead wire diameter


φ 0.8

Scale: 1/1 (mm)


F	Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
	AC 400 V		100 mA-6.3 A	500 A			1.0 <i>I</i> N until	
	DC 400 V	c <b>FLL</b> °us	100 IIIA-6.3 A	200 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	temperature stabilization	Within 30 min at 2.1 <i>I</i> <sub>N</sub>
	DC 400 V	- *3	100 mA-2.5 A	1500 A			occurs	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.
\*3: This specification is based on SOC internal testing.







Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated breaking current		Temp. rise	Current carrying capacity / Endurance test	Pre-arcing time-current characteristics
AC 500 V		<b>1</b> 00 mA 6 2 A *4	80 A		75 K or less	1.0 I <sub>N</sub> until temperature	Within 30 min
AC 400 V	<b>71</b>	100 mA-6.3 A *1	500 A		at 1.0 I <sub>N</sub>	stabilization occurs	at 2.1 I <sub>N</sub>
	6	1 A, 1.6 A, 2 A	200 A	Resistive circuit	-	*3	*4
DC 400 V	(2)	3 A, 3.15 A, 4 A 5 A, 6.3 A				3	
DC 400 V	100 mA-6.3 A *1	1500 A		75 K or less	1.0 / <sub>N</sub> until temperature	Within 30 min	
DC 250 V		100 IIIA-0.3 A 1	2000 A		at 1.0 / <sub>N</sub>	staḃilization occurs	at 2.1 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


٠.		.00 0) 0.00 0 114 .		it is bassed amondi. a	
*4:	Rated current	2.1 /N	2.75 IN	4.0 <i>I</i> N	10 <i>I</i> N
	1 A		0.3 s–2 s	0.095 s-0.5 s	0.01 s-0.03 s
	1.6 A, 2 A	Within 30 min	1 20 2	0.095 s–1 s	0.01 s-0.05 s
	3 A, 3.15 A 4 A, 5 A, 6.3 A		1 s–30 s	0.15 s–1 s	0.02 s-0.1 s

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

\*3: Endurance Test: After 100 cycles of 1.2 I<sub>N</sub> 1 h on / 15 min off, 1.5 I<sub>N</sub> is passed through the fuse for 1 h.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated breaking current		Temp. rise	Current carrying capacity / Endurance test	Pre-arcing time-current characteristics
AC 400 V DC 400 V	<b>71</b> (1);	1 A-20 A *1	500 A	Resistive	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 30 min at 2.1 / <sub>N</sub>
	(2)	10 A 15 A 20 A	500 A	circuit	-	*3	*4


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*3:</sup> Endurance Test: After 100 cycles of 1.2 /<sub>N</sub> 1 h on / 15 min off, 1.5 /<sub>N</sub> is passed through the fuse for 1 h.


\*4: 2 1 /<sub>N</sub> 2 75 /<sub>N</sub> 4 0 /<sub>N</sub> 10 /<sub>N</sub>

1:	2.1 / <sub>N</sub>	2.75 I <sub>N</sub>	4.0 I <sub>N</sub>	10 <i>I</i> N	
	Within 30 min	1 s–80 s	0.15 s–5 s	0.02 s-0.1 s	

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 700 V	c <b>'Al</b> l'us	1 A–4 A	500 A	Resistive circuit	75 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 30 min at 2.1 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

# SHV18


Inrush-withstand

RoHS-compliant\*2

### Representative pre-arcing time-current characteristics








Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 500 V	c <b>FN</b> °us	1 A–30 A	1000 A	Resistive circuit	-	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 30 min at 2.1 I <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 450 V	c <b>SN</b> °us	500 mA-6.3 A	200 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 30 min at 2.1 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# SHV22

Inrush-withstand


RoHS-compliant\*2

Pb free\*2

### Representative pre-arcing time-current characteristics








Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 500 V	c <b>'71</b> 2° us	1 A–10 A	1000 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 / <sub>N</sub> until temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

: 1 A–5 A Pb free

Over 5 A–10 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 Lead wire diameter  $\phi$  1.2 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 450 V	c <b>SN</b> ° us	6.3 A	400 A	Resistive circuit	120 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 30 min at 2.1 <i>I</i> <sub>N</sub>
DC 420 V		8 A–30 A	400 A				

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# SHV33

Inrush-withstand

RoHS-compliant\*2








Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 500 V	c <b>FLL</b> °us	10 A–30 A	500 A	Resistive circuit	150 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 500 V	-	1 A–10 A	500 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	-	Within 60 min at 2.1 / <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: 1 A-6.3 A Pb free

Over 6.3 A-10 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


# NSHV13

Protector


Inrush-withstand

RoHS-compliant\*2

### Representative pre-arcing time-current characteristics








Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Endurance test	Overload operation
AC 400 V DC 400 V	-	5 A–25 A	500 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	*3	Within 30 min at 2.1 <i>I</i> <sub>N</sub>


\*1: Customer-requested rated current values can be supplied from within the given range.

2: This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

\*3: After 100 cycles of 1.2 I<sub>N</sub> 1 h on / 15 min off, 1.5 I<sub>N</sub> is passed through the fuse for 1 h.







Scale: 1/1 (mm)

Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity / Endurance test	Overload operation
	100 mA to less than 1 A	200 A	Posistivo	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 / <sub>N</sub> until temperature stabilization occurs	Within 30 min at 2.1 / <sub>N</sub>	
DC 450 V	DC 450 V -	1 A–6.3 A	200 A	Resistive circuit	-	*3	*4

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


\*3: Endurance Test: After 100 cycles of 1.2 /<sub>N</sub> 1 h on / 15 min off, 1.5 /<sub>N</sub> is passed through the fuse for 1 h.

\*4: Rated current 2.1 /<sub>N</sub> 2.75 /<sub>N</sub> 4.0 /<sub>N</sub> 10 /<sub>N</sub>


:	Rated current	2.1 / <sub>N</sub>	2.75 I <sub>N</sub>	4.0 I <sub>N</sub>	10 <i>I</i> N
	1 A		0.3 s–2 s	0.095 s-0.5 s	0.01 s-0.03 s
	1.25 A-2.5 A	Within 30 min	1 s–30 s	0.095 s-1 s	0.01 s-0.05 s
	3 A-6.3 A		1 5–30 8	0.15 s–1 s	0.02 s-0.1 s

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

### Pre-arcing time-current characteristics







Scale: 1/1 (mm)

Maximum working voltage	Certification	Rated current (I <sub>N</sub> )	Maximum breaking current		Temp. rise	Endurance test	Overload operation
DC 500 V	-	10 A	30 A	Resistive circuit	75 K or less at 1.0 / <sub>N</sub>	*2	Within 30 min at 2.1 / <sub>N</sub>

<sup>\*1:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


# NSHV15

Protector


Inrush-withstand

RoHS-compliant\*2

### Representative pre-arcing time-current characteristics







Lead wire diameter  $\phi$  0.8


Scale: 1/1 (mm)


Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 700 V	-	1 A–4 A	500 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 30 min at 2.1 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

 $<sup>^{\</sup>star}2$ : After 100 cycles of 1.2  $I_N$  1 h on / 15 min off, 1.5  $I_N$  is passed through the fuse for 1 h.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.





25.4 Lead wire diameter φ 0.8 (1 A–8 A) Scale: 1/1  $\phi$  1.0 (Over 8 A to less than 15 A) (mm)

φ 1.2 (15 A–30 A)

Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 500 V	-	1 A–30 A	1000 A	Resistive circuit	75 K or less at 0.5 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


# NSHV23A

Protector


Inrush-withstand

RoHS-compliant\*2

### Representative pre-arcing time-current characteristics








		Scale: 1/
wire diameter	φ 1.0	(mm)


Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Endurance Test	Overload operation
AC 400 V DC 400 V	-	1 A–20 A	500 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	*3	Within 30 min at 2.1 <i>I</i> <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

\*3: After 100 cycles of 1.2 I<sub>N</sub> 1 h on / 15 min off, 1.5 I<sub>N</sub> is passed through the fuse for 1 h.





Rated vo	ltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Min. breaking current	Temp. rise	Overload operation
DC 450	0 V	-	100 A 125 A 150 A	10000 A	Resistive circuit	2.0 I <sub>N</sub>	50 K or less at 0.5 <i>I</i> <sub>N</sub>	*2


<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.


*2:	2.0 I <sub>N</sub>	3.0 / <sub>N</sub>	5.0 I <sub>N</sub>
	1 s–300 s	0.2 s-30 s	0.05 s–1 s

# DC450VPT2545

RoHS-compliant

Pb free







Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Min. breaking current	Temp. rise	Overload operation
DC 450 V	-	180 A 200 A 225 A	10000 A	Resistive circuit	2.0 I <sub>N</sub>	50 K or less at 0.5 <i>I</i> <sub>N</sub>	*2

<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.

r rougo corridor your re	odi 000 daloo lopi od	ontaire for rated carre
2.0 / <sub>N</sub>	3.0 / <sub>N</sub>	5.0 I <sub>N</sub>
1 s-300 s	0.2 s-30 s	0.05 s-1 s







Scale: 1/3 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) Rated breaking current		Min. breaking current	Temp. rise	Overload operation	
DC 450 V	-	250 A 300 A 350 A	16000 A	Resistive circuit	2.0 <i>I</i> <sub>N</sub>	50 K or less at 0.5 <i>I</i> <sub>N</sub>	*2

<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.


*2:	2.0 I <sub>N</sub>	3.0 I <sub>N</sub>	5.0 I <sub>N</sub>
	1 s–300 s	0.2 s-30 s	0.05 s-1 s


# DC500VBC625A

RoHS-compliant\*2










Scale: 1/2 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Min. breaking current	Temp. rise	Current carrying capacity	Overload operation
DC 500 V	-	5 A, 10 A, 15 A 20 A, 25 A 30 A, 35 A	1000 A	Resistive circuit	2.0 / <sub>N</sub>	75 K or less at 0.5 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.



Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rent	Min. breaking current	Temp. rise	Current carrying capacity	Overload operation
DC 500 V	-	5 A, 10 A, 15 A 20 A, 25 A 30 A, 35 A	1000 A	Resistive circuit	2.0 <i>I</i> <sub>N</sub>	75 K or less at 0.5 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>


\*1: Please contact your local SOC sales representative for rated currents which are not listed.


\*2: This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

# DC550VBI625C

RoHS-compliant\*2

## Representative pre-arcing time-current characteristics






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rent	Min. breaking current	Temp. rise	Current carrying capacity	Overload operation
DC 550 V			1000 A	Resistive	500 A	75 K or less	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 1 s at 500 A
DC 300 V	_	35 A	2000 A	circuit	70 A	at 0.5 I <sub>N</sub>		

\*1: Please contact your local SOC sales representative for rated currents which are not listed.

\*2: This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.



Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Min. breaking current	Temp. rise	Current carrying capacity	Overload operation
DC 600 V	-	30 A	1000 A	Resistive circuit	5.0 <i>I</i> N	75 K or less at 0.5 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 1 s at 5.0 / <sub>N</sub>


<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.

# DC500VBC635C


RoHS-compliant


Pb free

### Representative pre-arcing time-current characteristics










Scale: 1/2 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Min. breaking current	Temp. rise	Current carrying capacity	Overload operation
DC 500 V	-	5 A 15 A 30 A	2000 A	Resistive circuit	2.0 / <sub>N</sub>	50 K or less at 0.7 <i>I</i> <sub>N</sub>	4 h or more at 1.1 / <sub>N</sub>	*2


<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.


	,		
*2:	2.0 /N	3.0 /N	5.0 <i>I</i> N
	0.5 s-100 s	0.1 s-15 s	0.05 s-1 s

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.









Scale: 1/2 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	/ <sub>N</sub> ) Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
40 0F0 V	c <b>FL</b> us	40 A	1500 A	PF	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 4 min at 2.0 I <sub>N</sub>
AC 250 V	PS E	50 A 60 A	1500 A	PF 0.7–0.8	At 1.15 I <sub>N</sub> , 140 K or less at the center, 75 K or less at the contact	1.3 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.6 / <sub>N</sub> Within 4 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.


# AC450VBL1030C


RoHS-compliant

Pb free











Scale: 1/2 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rent	Min. breaking current	Temp. rise	Current carrying capacity	Overload operation
AC 450 V	-	60 A	500 A	Resistive circuit	2.0 / <sub>N</sub>	150 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.







Scale: 1/2 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		oreaking rent	Temp. rise	Current carrying capacity	Overload operation
DC 72 V	-	50 A 70 A	1000 A	Resistive circuit	75 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.


# DC500VBL1030F

RoHS-compliant

Pb free








Scale: 1/2 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Min. breaking current	Temp. rise	Current carrying capacity	Overload operation
DC 500 V	-	60 A	500 A	Resistive circuit	5.0 / <sub>N</sub>	25 K or less at 0.5 <i>I</i> <sub>N</sub>	1.0 /N until temperature stabilization occurs	Within 1 s at 5.0 / <sub>N</sub>

<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.



Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rent	Min. breaking current	Temp. rise	Current carrying capacity	Overload operation
DC 500 V	c <b>FU</b> °us	F A FO A	1000 A				4.0.4	
AC 500 V	c <b>744</b> us	5 A–50 A	500 A	Resistive circuit	2.0 / <sub>N</sub>	150 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>
DC 500 V	-	5 A–40 A	2000 A				occurs	


<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.

# 500VBL1030A


RoHS-compliant


Pb free

### Representative pre-arcing time-current characteristics











Scale: 1/2 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Min. breaking current	Temp. rise	Current carrying capacity	Overload operation
DC 500 V	c <b>FU</b> °us	5 4 50 4	1000 A			At 1.0 / <sub>N</sub>	404 "	
AC 500 V	c <b>712</b> us	5 A-50 A	500 A	Resistive circuit	2.0 / <sub>N</sub>	5 A-25 A 100 K or less 30 A 120 K or less	stabilization	Within 2 min at 2.0 <i>I</i> <sub>N</sub>
DC 500 V	-	5 A–40 A	2000 A			35 A-50 A 150 K or less	occurs	


<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		oreaking rent	Min. breaking current	Temp. rise	Overload operation
DC 500 V	-	225 A	2000 A	Resistive circuit	5.0 <i>I</i> <sub>N</sub>	50 K or less at 0.5 <i>I</i> <sub>N</sub>	0.05 s–1 s at 5.0 / <sub>N</sub>

<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.







Scale: 1/3 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		oreaking rent	Min. breaking current	Temp. rise	Overload operation
DC 450 V	-	250 A 350 A	5000 A	Resistive circuit	2.0 I <sub>N</sub>	50 K or less at 0.5 <i>I</i> <sub>N</sub>	0.05 s–1 s at 5.0 / <sub>N</sub>


<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.

# PT4065

RoHS-compliant


Pb free






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current	Min. breaking current	Current carrying capacity	Overload operation
DC 800 V		400 A	10000 A (τ ≦ 1 ms)	20.0 / <sub>N</sub>		-
DC 500 V	-	400 A	20000 A	2.0 /N	0.75 I <sub>N</sub> until temperature stabilization occurs	1 s–300 s
DC 300 V		500 A	(τ ≦ 1 ms)	2.0 IN		at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Please contact your local SOC sales representative for rated currents which are not listed.








Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated bre currer		Endurance test	Pre-arcing time- current characteristics
AC250V	<b>71</b> °	80 mA 100 mA 125 mA 160 mA 200 mA 250 mA 315 mA 400 mA 500 mA 630 mA 800 mA 1 A 1.25 A 1.6 A 2 A 2.5 A 3.15 A 4 A 5 A	35 A or 10 I <sub>N</sub> , whichever is greater	Resistive circuit	*1	*2

\*1: After 100 cycles of 1.2 I<sub>N</sub> 1 h on / 15 min off, 1.5 I<sub>N</sub> is passed through the fuse for 1 h.

*2:	Rated current	2.1 /N	2.75 /N	4.0 /N	10 /N	
	80 mA, 100 mA	Within 30 min	0.01 s-0.5 s	0.003 s-0.1 s	Within 0.02 s	
	125 mA-6.3 A	VVIUIIII 30 IIIIII	0.05 s-2 s	0.01 s-0.3 s	VVIIIIII U.UZ S	







Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> )		oreaking rent	Endurance test	Test at elevated temperature	Pre-arcing time-current characteristics
AC 250 V		315 mA 400 mA 500 mA 630 mA 800 mA 1 A 1.25 A 1.6 A 2 A 2.5 A 3.15 A 4 A 5 A 6.3 A	35 A or 10 I <sub>N</sub> , whichever is greater		*2	*3	*4

- \*1: Fuses with rated currents of less than 1A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- \*2: After 100 cycles of 1.2  $I_N$  1 h on / 15 min off, 1.5  $I_N$  is passed through the fuse for 1 h.


	A current of 1.1 /N is p	assed inrough the lus	e ior i n al a lemperai	ure or 70±2 C.	
*4:	2.1 I <sub>N</sub>	2.75 I <sub>N</sub>	4.0 / <sub>N</sub>	10 / <sub>N</sub>	
	Within 2 min	0.6 s–10 s	0.15 s–3 s	0.02 s-0.3 s	

Time-lag

Representative pre-arcing time-current characteristics








Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated breaking current		Temp. rise	Current carrying capacity / Endurance test	Test at elevated temperature	Pre-arcing time-current characteristics
	c <b>711</b> ° us	1 A 1.25 A 1.6 A	150 A	150 A Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	-	Within 30 min at 2.1 / <sub>N</sub>
AC 250 V	(2)	2 A 2.5 A 3.15 A	150 A		-	*1	*2	*3
	PS	4 A 5 A 6.3 A	100 A	PF 0.7–0.8	At 1.0 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.0 I <sub>N</sub> until constant temperature is obtained on each part	-	Within 30 min at 2.1 I <sub>N</sub>


\*1: Endurance Test: After 100 cycles of 1.2 I<sub>N</sub> 1 h on / 15 min off, 1.5 I<sub>N</sub> is passed through the fuse for 1 h.

\*2: A current of 1.1 /<sub>N</sub> is passed through the fuse for 1 h at a temperature of 70±2 °C.
\*3: 2.1 h, 2.75 h, 4.0 h, 10 h,

2.1 I <sub>N</sub>	2.75 I <sub>N</sub>	4.0 / <sub>N</sub>	10 <i>I</i> N
Within 2 min	0.6 s-10 s	0.15 s–3 s	0.02 s-0.3 s







Lead wire diameter


Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated breaking current		Temp. rise	Current carrying capacity / Endurance test	Test at elevated temperature	Pre-arcing time-current characteristics
	c <b>AL</b> °us	1 A 1.25 A 1.6 A	150 A	Resistive	75 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	-	Within 30 min at 2.1 I <sub>N</sub>
AC250V	(\$)	2 A 2.5 A 3.15 A	150 A	circuit	-	*1	*2	*3
	(PS) E	4 A 5 A 6.3 A	100 A	PF 0.7–0.8	At 1.0 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.0 I <sub>N</sub> until constant temperature is obtained on each part	-	Within 30 min at 2.1 / <sub>N</sub>


\*1: Endurance Test: After 100 cycles of 1.2 I<sub>N</sub> 1 h on / 15 min off, 1.5 I<sub>N</sub> is passed through the fuse for 1 h.
\*2: A current of 1.1 I<sub>N</sub> is passed through the fuse for 1 h at a temperature of 70±2 °C.

\*3:

2.1 I <sub>N</sub>	2.75 I <sub>N</sub>	4.0 / <sub>N</sub>	10 <i>I</i> N
Within 2 min	0.6 s-10 s	0.15 s–3 s	0.02 s-0.3 s








Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated breaking current		Endurance test	Pre-arcing time- current characteristics
AC 250 V	<b>91</b> ° <b>©</b> . (S)	400 mA 500 mA 630 mA 800 mA 1 A 1.25 A 1.6 A 2 A 2.5 A 3.15 A 4 A 5 A 6.3 A	1500 A	PF 0.7–0.8	*1	*2


\*1: After 100 cycles of 1.2 I<sub>N</sub> 1 h on / 15 min off, 1.5 I<sub>N</sub> is passed through the fuse for 1 h.

\*2:

•		•	•	
Rated current	2.1 /N	2.75 In	4.0 /N	10 <i>I</i> N
400 mA-3.15 A	Within 30 min	0.01 s-2 s	0.003 s-0.3 s	Within 0.02 s
4 A-6.3 A	vviuiiii 30 IIIIII	0.01 s-3 s	0.003 8-0.3 8	VVILIIII U.UZ S








Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated b	reaking ent	Endurance test	Test at elevated temperature	Pre-arcing time-current characteristics
AC 250 V		1 A 1.25 A 1.6 A 2 A 2.5 A 3.15 A 4 A 5 A 6.3 A	1500 A	PF 0.7–0.8	*1	*2	*3
	c <b>Al</b> us  S  PS  PS	8 A 10 A					


*2	<ul> <li>*1: After 100 cycles of 1.2 I<sub>N</sub> 1 h on / 15 min off, 1.5 I<sub>N</sub> is passed through the fuse for 1 h.</li> <li>*2: A current of 1.1 I<sub>N</sub> is passed through the fuse for 1 h at a temperature of 70±2 °C.</li> </ul>							
*3	3: Rated current 2.1 I <sub>N</sub> 2.75 I <sub>N</sub> 4.0 I <sub>N</sub> 10 I <sub>N</sub>							
	1 A-3.15 A	Within 30 min	0.75 0.00 0	0.095 s-5 s	0.01 a 0.15 a			
	4 A-10 A	VVIUIIII 30 IIIIII	0.75 s–80 s	0.15 s–5 s	0.01 s–0.15 s			

\*4: 1 A-6.3 A 8 A-10 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Lead wire diameter  $\phi$  0.8 (1 A–6.3 A)  $\phi$  1.0 (8 A–10 A)

Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated breaking current		Endurance test	Test at elevated temperature	Pre-arcing time-current characteristics
AC 250 V	c SN us  S  PE	1 A 1.25 A 1.6 A 2 A 2.5 A 3.15 A 4 A 5 A 6.3 A 8 A 10 A	1500 A	PF 0.7–0.8	*1	*2	*3

- \*1: After 100 cycles of 1.2  $I_N$  1 h on / 15 min off, 1.5  $I_N$  is passed through the fuse for 1 h.
- \*2: A current of 1.1  $I_N$  is passed through the fuse for 1 h at a temperature of 70±2 °C.


_	., ,	3				
3:	Rated current	2.1 / <sub>N</sub>	2.75 I <sub>N</sub>	4.0 I <sub>N</sub>	10 <i>I</i> N	
	1 A-3.15 A	Within 30 min	0.75 s–80 s	0.095 s–5 s	0.01 s–0.15 s	
	4 A-10 A	VVIUIIII 30 IIIIII	0.75 S-60 S	0.15 s-5 s	0.01 8-0.15 8	

\*4: 1 A-6.3 A Pb free

8 A–10 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Lead wire diameter φ 1.2

Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	c <b>FN</b> °us	4 4 20 4	400 A	PF	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 / <sub>N</sub>
AC 250 V	PS	1 A-20 A	100 A	PF 0.7–0.8	At 1.15 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.3 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.6 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# DC125VTLKR

Inrush-withstand


RoHS-compliant\*2

Pb free\*2

### Representative pre-arcing time-current characteristics







Scale:	1/1
(mm	)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 125 V	c <b>Al</b> l us	800 mA–35 A	1000 A	Resistive circuit	110 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


: 8 A or less Pb free

Over 8 A–35 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Note: Rated currents of over 15 A-20 A are soldered internally.

Scale: 1/1 (mm)

Pb free\*2

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	100 mA-15 A	10000 A	PF	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>	
	<b>A</b> L	Over 15 A–20 A	10000 A	PF 0.7–0.8	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 2 mìn at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


# CES6 N1

Inrush-withstand


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics







Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(I) (I)	100 mA–15 A	10000 A	PF	70 K or less at 1.1 I <sub>N</sub>	1.1 / <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
AC 123 V	PS *2	100 IIIA-13 A	500 A	0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 <i>I</i> <sub>N</sub>


- \*1: Customer-requested rated current values can be supplied from within the given range.
- Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 100 mA-8 A Over 8 A-15 A

Pb free

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>100</sup> mA-8 A, over 15 A-20 A Pb free Over 8 A-15 A





Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(h) (B)	100 mA-15 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: 100 mA-8 A Pb free

Over 8 A–15 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive


# CES7 N1


Inrush-withstand

RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics





Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AO 405 V	(h) <b>(B</b> •	100 mA 15 A	10000 A	PF	70 K or less at 1.1 I <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
AC 125 V	PS *2	- 100 mA-15 A	500 A	0.7–0.8	At 1.1 / <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.


3: 100 mA-8 A Pb free

Over 8 A–15 A This p

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	40.050 V	100 mA-10 A	200 A	PF	70 K or less	or more after	Within 60 min at 1.35 / <sub>N</sub>
AC 250 V	<b>71</b> °	Over 10 A–15 A	100 A	0.7–0.8	at 1.1 / <sub>N</sub>	temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: 100 mA-8 A Over 8 A-15 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the


# **CES14 N1**

Inrush-withstand


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(I) (I)	100 mA–10 A	200 A	PF	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 / <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
AC 250 V	P\$ *2	100 IIIA-10 A	100 A	0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


Customer-requested rated current values can be supplied from within the given range.

Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.


100 mA-8 A

Over 8 A-10 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
_	<b>A</b>	Over 10 A–15 A	100 A	PF 0.7–0.8	70 K or less at 1.1 I <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
AC 250 V	PS E	Over 10 A-15 A	100 A	0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

# CES15


Inrush-withstand

RoHS-compliant\*2

Pb free\*2







Lead wire diameter  $\phi$  0.8 (100 mA–8 A)  $\phi$  1.2 (Over 8 A–30 A)

Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>71</b> ° (1)°,	100 mA–15 A	200 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
	c <b>FN</b> °us	Over 15 A–30 A	200 A	0.7–0.8	-	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2: 100</sup> mA-8 A, over 15 A-25 A Pb free

Over 8 A-15 A, over 25 A-30 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.





Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
	<b>W (F</b> )	100 mA–15 A	200 A		70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
AC 250 V	c <b>FL</b> us	Over 15 A–25 A	200 A	PF 0.7–0.8	-	1.0 / <sub>N</sub> until temperature stabilization occurs	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>
	P\$ *2	100 mA-25 A	100 A		At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Over 8 A-15 A


This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

<sup>\*3: 100</sup> mA-8 A, over 15 A-25 A Pb free







Scale: 1/1 (mm)

Ra	ated voltage	Certifi	cation	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
,	AC 250 V	<b>W</b>	<b>®</b> ;	1 A–30 A	10000 A	PF 0.7–0.8	120 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

\*2: 1 A-12 A

Pb free

Over 12 A-30 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


# KST2 N1

Inrush-withstand


RoHS-compliant\*2

Pb free\*2

### Representative pre-arcing time-current characteristics







Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>FL (1)</b> ;	- 6.3 A–30 A	10000 A	PF	120 K or less at 1.0 I <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>
AC 250 V	(PS)	6.5 A=30 A	1500 A	0.7–0.8	At 1.0 / <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.0 / <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.5 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


\*2: 6.3 A–12 A

Pb free

Over 12 A-30 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







φ 0.5 (62 mA–5 A) Lead wire diameter φ 0.8 (Over 5 A-10 A) φ 1.0 (Over 10 A–15 A)

Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(h) (b)	62 mA–5 A	- 10000 A	PF 0.7–0.8	70 K or less at 1.1 / <sub>N</sub>	1.1 /N for 15 min or more after temperature stabilization occurs  1.0 /N for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>
	<b>FL</b> (1)	Over 5 A–10 A			90 K or less at 1.1 / <sub>N</sub>		
	<b>(B</b> )	Over 10 A–15 A			75 K or less at 1.0 I <sub>N</sub>		

\*1: Customer-requested rated current values can be supplied from within the given range.

62 mA-8 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the Over 8 A-15 A RoHS Directive.


## **MQ1 N1**

Normal-acting


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics







Lead wire diameter φ 0.5 (62 mA-5 A) φ 0.8 (Over 5 A-10 A)

Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V		62 mA–5 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs  1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>
	<b>FL</b> (1)	Over 5 A–10 A			90 K or less at 1.1 / <sub>N</sub>		
	PS *2	62 mA–10 A	500 A		At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact		

Customer-requested rated current values can be supplied from within the given range.


Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

62 mA-8 A Pb free Over 8 A-10 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(H) (B)	62 mA–5 A	10000 A		70 K or less at 1.1 / <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after	
	<b>FL</b> ® <b>LR</b>	Over 5 A–10 A		PF	90 K or less at 1.1 / <sub>N</sub>	temperature stabilization occurs	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>
7.0 120 V	∰.	Over 10 A–15 A	10000 A	0.7–0.8	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	

\*1: Customer-requested rated current values can be supplied from within the given range.

2: 62 mA-8 A Pb free

Over 8 A–15 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


### **MQ2 N1**

Normal-acting


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics







Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(I) <b>(I)</b>	62 mA–5 A	10000 A		70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature	Within 60 min at 1.35 / <sub>N</sub>
	<b>FL (B</b> ·	Over 5 A–10 A	10000 A	PF	90 K or less at 1.1 / <sub>N</sub>	stabilization occurs	
AC 123 V	<b>₽\$</b> *2	62 mA–10 A	500 A	0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 <i>I</i> <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.


\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

\*3: 62 mA-8 A Pb free

Over 8 A-10 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







(Over 10 A-15 A)

Lead wire diameter  $\phi$  0.5 (62 mA-3 A)  $\phi$  0.8 (Over 3 A-10 A)

φ 1.0

Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	62 mA-3 A	100 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>	
AC 250 V	<b>7</b> 1°	Over 3 A–15 A	100 A	0.7–0.8	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 / <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Over 8 A–15 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


### **MQ3 N1**

Normal-acting


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics








Lead wire diameter  $\phi$  0.5

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>(L) (D)</b>	62 mA–3 A	100 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 / <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub>
AC 250 V	<b>₽\$</b> *2	02 IIIA–3 A	100 A	0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 <i>I</i> <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>2: 62</sup> mA-8 A Pb free

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
(I) (I)	62 mA–3 A	100 A	PF	70 K or less at 1.1 I <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>	
AC 250 V	50 V 100 A Over 3 A–15 A	PF 0.7–0.8	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>		

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Over 8 A–15 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


### **MQ4 N1**

Normal-acting


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics








Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(h) (B)	004.04		PF	70 K or less at 1.1 / <sub>N</sub>	1.1 / <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
AC 250 V	PS *2	62 mA–3 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2: 62</sup> mA-8 A Pb fre

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Lead wire diameter  $\phi$  0.5 (100 mA–1 A)  $\phi$  0.8 (Over 1 A–10 A)  $\phi$  1.0 (Over 10 A–15 A)

Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>⊕ ⊕</b>	100 mA-3.5 A			70 K or less	1.1 I <sub>N</sub> for 15 min or more after temperature	
	Over 3.5 A–8 A	100 A	PF	at 1.1 / <sub>N</sub>	stabilization occurs	Within 60 min at 1.35 I <sub>N</sub>	
	<b>51</b> °	Over 8 A–15 A	100 A	0.7–0.8	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Over 8 A–15 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


# MT3 N1

Inrush-withstand


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics







Lead wire diameter  $\phi$  0.5


φ 0.5 (100 mA–1 A) φ 0.8 (Over 1 A–3.5 A)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>(1111111111111</b>	100 mA–3.5 A	400 A	PF 0.7–0.8	70 K or less at 1.1 / <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
AC 250 V	PS *2	100 IIIA-3.3 A	100 A	0.7–0.8	At 1.1 / <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2: 100</sup> mA-8 A Pb free

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Lead wire diameter #

 $\phi \ 0.8 \quad \text{(Over 3.5 A -10 A)}$  $\phi \ 1.0 \quad \text{(Over 10 A-15 A)}$ 


Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	8	Over 3.5 A–8 A	100 A	PF 0.7–0.8	70 K or less or more af	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
	<b>A</b> L	Over 8 A–15 A			70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>
	PS	Over 3.5 A–15 A			At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> Over 3.5 A-8 A Pb free Over 8 A-15 A This pro







Lead wire diameter

φ 0.5 (100 mA–1 A) φ 0.8 (Over 1 A-10 A) φ 1.0 (Over 10 A–15 A)


Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
	(F) <b>(B</b> )	100 mA-3.5 A			70 K or less	1.1 I <sub>N</sub> for 15 min or more after temperature	
AC 250 V	<b>A</b> L°	Over 3.5 A–8 A	100 A	PF 0.7–0.8	at 1.1 / <sub>N</sub>	stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
		Over 8 A–15 A			70 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
	(H)	100 mA-3.5 A	- 500 A		70 K or less	1.1 /N for 15 min	Within 2 min at 2.0 <i>I</i> <sub>N</sub>
DC 125 V		Over 3.5 A–8 A			at 1.1 / <sub>N</sub>		
DC 125 V	<b>91</b> °	Over 8 A–15 A		circuit	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the Over 8 A-15 A RoHS Directive.

<sup>\*2: 100</sup> mA–8 A Pb free







Lead wire diameter


r φ 0.5 (100 mA–1 A) φ 0.8 (Over 1 A–3.5 A)

Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(I) (I)		100 A	PF	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
AC 250 V	PS *2	100 mA-3.5 A	100 A	0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>
DC 125 V	(UL)		500 A	Resistive circuit	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Lead wire diameter  $\phi$  0.

φ 0.8 (Over 3.5 A–10 A) φ 1.0 (Over 10 A–15 A)

Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>5</b> 1/°	Over 3.5 A–8 A			70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
	Over 8 A–15 A	100 A	PF 0.7–0.8	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs		
	PS	Over 3.5 A–15 A	.5 A–15 A		At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>
DC 125 V	<b>91</b> °	Over 3.5 A–8 A	500 A	Resistive	70 K or less at 1.1 / <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
DC 125 V	277	Over 8 A–15 A	500 A	circuit	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


<sup>\*2:</sup> Over 3.5 A-8 A Pb free

Over 8 A–15 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
	(H) (∰)	▼ 100 mA–3.5 A			70 K or less		
AC 250 V	AC 250 V	Over 3.5 A–8 A	100 A	PF	at 1.1 / <sub>N</sub>		Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>
AC 250 V		Over 8 A–15 A	100 A	0.7–0.8	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Pb free

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


### **MT4 N1**

Inrush-withstand


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics








Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>(I) (S)</b> •	100 mA-3.5 A		PF	70 K or less at 1.1 I <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
AC 250 V	P\$ *2	100 IIIA-3.3 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2: 100</sup> mA-8 A Pb Over 8 A-15 A Th

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.








Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
	<b>- \</b> \°	Over 3.5 A–8 A			70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
AC 250 V	744	Over 8 A–15 A		PF 0.7–0.8	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>
	PS	Over 3.5 A–15 A			At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Over 8 A–15 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> Over 3.5 A–8 A Pb free








Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
	(l) <b>(B</b> •	100 mA-3.5 A			70 K or less	1.1 I <sub>N</sub> for 15 min or more after temperature	
AC 250 V	AC 250 V Over 3.5 A–8 A Over 8 A–15 A	100 A	PF	at 1.1 / <sub>N</sub>	stabilization occurs		
AC 250 V		Over 8 A–15 A	100 A	0.7–0.8	70 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
	(II)	100 mA-3.5 A		Resistive	70 K or less	1.1 I <sub>N</sub> for 15 min or more after temperature	Within 2 min at 2.0 <i>I</i> <sub>N</sub>
DC 125 V		Over 3.5 A–8 A	500 A		at 1.1 / <sub>N</sub>	stabilization occurs	
DO 123 V	Over 8 A–15 A	000 A	circuit	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs		


<sup>\*1:</sup> \*2: Customer-requested rated current values can be supplied from within the given range.

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the Over 8 A-15 A RoHS Directive.

<sup>100</sup> mA-8 A Pb free









Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(l) <b>(f)</b>		100 A	PF	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
AC 250 V	PS *2	100 mA-3.5 A	100 A	0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at t he contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>
DC 125 V	(I)		500 A	Resistive circuit	70 K or less at 1.1 / <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.








Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
	<b>51</b> 1°	Over 3.5 A–8 A			70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
AC 250V	AC 250V Over 8 A–15 A	Over 8 A–15 A	100 A	PF 0.7–0.8	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
		Over 3.5 A–15 A			At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>
DC 425V	\$	Over 3.5 A–8 A		Resistive	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
DC 125V Over 8	Over 8 A–15 A	500 A	circuit	70 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs		

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


<sup>\*2:</sup> Over 3.5 A-8 A Pb free

Over 8 A–15 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Lead wire diameter  $\phi$  0.8

Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(h) <b>(b</b> •	100 mA–3 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 / <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


### MT8

Inrush-withstand


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics









Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(h) <b>(£</b> :	100 mA–3 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.







Scale: 1/1 (mm)

Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 42 V DC 42 V	-	100 mA-20 A	100 A	Resistive circuit	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

\*2: 100 mA-8 A Pb free

Over 8 A=20 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

# PNT5


Protector

Inrush-withstand


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics









Maximum working voltage	Certification	Rated current (I <sub>N</sub> ) *1	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 100 V	-	100 mA–10 A	100 A	Resistive circuit	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 s at 2.0 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.







Scale: 2/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	AC 405 V	00 . 4 .40 4	50.4	PF 0.7–0.8	70 K or less	or more after	Within 10 min at 1.5 I <sub>N</sub>
AC 125 V	<b>⊕</b>	62 mA–10 A	50 A	PF 0.95–1	at 1.0 / <sub>N</sub>	temperature stabilization occurs	Within 60 s at 2.0 I <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

### NQ3


Quick-acting

RoHS-compliant\*2

### Representative pre-arcing time-current characteristics








Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
A.C. 250.V	<b>91</b> °	CO A . 40 A		Resistive circuit	70 K or less	or more after at 1.5	Within 10 min at 1.5 I <sub>N</sub>
AC 250 V	<b>⊕</b>	62 mA-10 A	50 A	PF 0.95–1	at 1.0 I <sub>N</sub>	temperature stabilization occurs	Within 60 s at 2.0 I <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 2/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(II)	100 4 10 4	50 A	PF 0.7–0.8	70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after	Within 10 min at 1.5 I <sub>N</sub>
	<b>⊕</b>	- 100 mA–10 A		PF 0.95–1		temperature stabilization occurs	Within 60 s 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

# NT3


Inrush-withstand

RoHS-compliant\*2

### Representative pre-arcing time-current characteristics








Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250V	<b>7</b> L°	400 4 40 4	50A -	Resistive circuit	70 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 10 min at 1.5 /N
	<b>⊕</b>	- 100 mA–10 A		PF 0.95–1			Within 60 s 2.0 I <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		oreaking rent	Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(H)	3 A–15 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


\*2: 3 A-12 A Pb free

Over 12 A-15 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

## SKM7 | Inrush-withstand | RoHS-compliant\*2 | Pb free\*2

Representative pre-arcing time-current characteristics






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>71</b> (B.	100 mA-30 A	1500 A	PF 0.7–0.8	75 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

\*2: 100 mA-12 A Pb free

Over 12 A-30 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>A</b> L <b>(</b> E)	100 mA-30 A	1000 A	Resistive circuit	100 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

\*2: 100 mA-12 A Pb free

Over 12 A–30 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the


# **SKM10 N1**

Inrush-withstand


RoHS-compliant\*2

Pb free\*2

### Representative pre-arcing time-current characteristics








Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 050 V	<b>71</b> ° <b>(</b> (1);	4 4 05 4	1000 A	Resistive circuit	100 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
AC 250 V	PS	- 1 A-25 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 I <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

2: 1 A–12 A Pb free

Over 12 A-25 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		oreaking rent	Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(h) <b>(£</b> •	80 mA-6 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 / <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


### SL4

Normal-acting


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics









Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>⊕ ઉ</b>	80 mA–2 A	100 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.







φ 0.8

Lead wire diameter

Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current	Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(l) <b>(B</b> •	80 mA–3 A	10000 A PF 0.7–0.8	70 K or less at 1.1 / <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


### SQ8

Normal-acting


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics








Rated voltage	Certification	Rated cu	rrent (I <sub>N</sub> ) Rat	ited bro	eaking ent	Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(l) (g)	80 mA	A–3 A 1000	00 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

SS<sub>1</sub> Normal-acting RoHS-compliant Pb free

#### Representative pre-arcing time-current characteristics







		, ,
^	Current carrying	Overload
е	canacity	oneration

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		oreaking rent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(h) (1)	50 mA-5 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 I <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# **SS1 N1**

Normal-acting


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics







		Scale: 1/2
vire diameter	φ 0.8	(mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(l) <b>(f</b> )	50 mA-5 A	10000 A	PF	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 / <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub>
AC 250 V	P\$ *2	50 IIIA-5 A	500 A	0.7–0.8	At 1.1 / <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

SS2 Normal-acting


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(h) (B)	50 mA–5 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 / <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# SS2 N1

Normal-acting


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics








Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(h) <b>(B</b> •	50 mA–5 A	10000 A	PF	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub>
AC 250 V	PS *2	30 IIIA-3 A	500 A	0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

SS5 Normal-acting RoHS-compliant\*2 Pb free\*2

#### Representative pre-arcing time-current characteristics







Lead wire diameter φ 0.8 (Over 5 A-8 A) φ 1.0 (Over 8 A-15 A) Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(h) (B)	Over 5 A–8 A	200 A	PF	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
AC 125 V	<b>71</b>	Over 8 A–15 A	10000 A	0.7–0.8	70 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Over 8 A-15 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


**SS6** 

Normal-acting


RoHS-compliant\*2

Pb free\*2

### Representative pre-arcing time-current characteristics







Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(h) (f)	Over 5 A–8 A	200 A	PF	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub>
AC 125 V	<b>FU</b> * <b>(IP</b> *	Over 8 A–15 A	10000 A	0.7–0.8	70 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 2 min at 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


<sup>\*2:</sup> Over 5 A-8 A Pb free

Over 5 A-8 A

Over 8 A-15 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(h) <b>(f</b> )	Over F.A. 9.A	200 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
AC 250 V	Over 5 A–8 A	Over 5 A=6 A	100 A		At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>
AC 425 V	<b>71</b> ° <b>®</b> •	Over 8 A–15 A	10000 A		70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
AC 125 V	PS	Over o A-15 A	500 A		At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


Pb free Over 8 A-15 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> Over 5 A–8 A







Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		oreaking rent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	(l) <b>(B</b> •	Over 5 A–8 A	200 A		70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
AC 250 V	C 250 V Over 5 A	Over 5 A=6 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>
AC 425 V	<b>A1</b> ° <b>(</b>	Over 8 A–15 A	10000 A		70 K or less at 1.0 <i>I</i> <sub>N</sub>	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
AC 125 V	PS	Over o A-15 A	500 A		At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


Pb free Over 8 A-15 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> Over 5 A–8 A







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
		100 mA-1 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	occurs at 1.35 /	
AC 250 V	<b>⊕ ⊕</b>	Over 1 A–8 A					Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>
AC 250 V	c <b>'911</b> °us	Over 8 A–30 A	200 A		-		

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Pb free

Over 8 A-30 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


### **ST3 N1**

Inrush-withstand


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics








Lead wire diameter  $\phi$  0.8

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V		100 mA–1 A	10000 A	70 K or less at 1.1 I <sub>N</sub> PF 0.7–0.8  At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact		occurs at 1.35 at 1.1 /N until Within 2 r	
	<b>€ €</b>	Over 1 A–8 A	200 A				Within 60 min at 1.35 / <sub>N</sub>
	PS *0	100 mA-1 A	500 A		140 K or less		Within 2 min at 2.0 I <sub>N</sub>
	E Z	Over 1 A–8 A	100 A		is obtained on each part		


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2: 100</sup> mA-8 A

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
	100 mA-1 A	10000 A		70 K or less	1.1 I <sub>N</sub> for 15 min or more after		
AC 250 V	(L) (F)	Over 1 A–8 A		PF 0.7–0.8	at 1.1 / <sub>N</sub>	temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>
AC 250 V	c <b>SN</b> us	Over 8 A–30 A	200 A		-	1.0 I <sub>N</sub> until constant temperature is obtained on each part	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

Pb free

Over 8 A-30 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


# **ST4 N1**

Inrush-withstand


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics









Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V		100 mA–1 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	occurs at 1.35 1.1 I <sub>N</sub> until Within 2 constant at 2.0 I	
	<b>⊕ ⊕</b>	Over 1 A–8 A	200 A				Within 60 min at 1.35 I <sub>N</sub>
	PS *2	100 mA–1 A	500 A		0.7–0.8  At 1.1 / <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact		Within 2 min at 2.0 <i>I</i> <sub>N</sub>
	E 2	Over 1 A–8 A	100 A			temperature is obtained on each part	

<sup>1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2: 100</sup> mA–8 A

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(l) <b>(B</b> •	100 mA–8 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub>
	-» @				200 K or less	1.0 / <sub>N</sub> until temperature	Within 2 min at 2.0 I <sub>N</sub>
DC 125 V		Over 8 A–30 A	500 A	Resistive circuit	at 1.0 I <sub>N</sub>	stabilization occurs	


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

\*2: 100 mA-8 A

100 mA-8 A Pb free Over 8 A-30 A This p

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(h) (B)	100 mA-8 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>
	<b>FL</b>	Over 8 A–15 A	500 A		200 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	
	PS *2	100 mA-15 A			At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	
DC 125 V	<b>91</b> ° (1);	Over 8 A–15 A		Resistive circuit	200 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	


\*3: 100 mA-8 A

Over 8 A-15 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.
\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(h) <b>(B</b> •	100 mA–8 A	10000 A	0000 A PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
	<b>71 (1)</b>	Over 8 A–30 A			120 K or less at 0.9 / <sub>N</sub>	0.9 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
DC 125 V	(h) <b>(B</b> •	100 mA–8 A	500 A	Resistive	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 2 min at 2.0 <i>I</i> <sub>N</sub>
DC 125 V -	<b>91 (F.</b>	Over 8 A–30 A		circuit	120 K or less at 0.9 / <sub>N</sub>	0.9 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


Pb free Over 8 A-30 A

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2: 100</sup> mA–8 A







Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(h) (B)	100 mA–8 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
	<b>71</b> ° (1)°,	Over 8 A–15 A	500 A		120 K or less at 0.9 I <sub>N</sub>	0.9 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>
	P\$ *2	100 mA-15 A			At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	
DC 125 V	(l) (f)	100 mA–8 A		Resistive circuit	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	
DC 125 V	<b>71</b> ° (f);	Over 8 A–15 A			120 K or less at 0.9 / <sub>N</sub>	0.9 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


Over 8 A–15 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

<sup>\*3: 100</sup> mA-8 A Pb free







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	<i>7</i> 1°	80 mA–5 A	200 A	PF 0.7–0.8	70 K or less at 1.1 / <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


### SU<sub>2</sub>

Normal-acting


RoHS-compliant\*2

Pb free\*2

### Representative pre-arcing time-current characteristics









	Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
	AC 125 V	<b>71</b> 1°	100 mA–5 A	200 A -	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 / <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
		<b>74</b>	Over 5 A–20 A		Resistive circuit	-	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 2 min at 2.0 / <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: 100 mA-15 A Pb free
  - Over 15 A-20 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 60 V	<b>71</b> °	Over 5 A–20 A	100 A	Resistive circuit	-	1.0 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the Over 15 A-20 A


# LLD6500


Protector


Normal-acting

RoHS-compliant\*1

### Pre-arcing time-current characteristics








(mm)


Maximum working voltage	Certification	Rated current (I <sub>N</sub> )	Maximum breaking current		Temp. rise	Current carrying capacity	Overload operation
DC 600 V	-	15 A	500 A	Resistive circuit	150 K or less at 1.0 / <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs	Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.

<sup>\*2:</sup> Over 5 A-15 A








Rated voltage	Certification	Rated current (I <sub>N</sub> )	Rated breaking current		Endurance test	Test at elevated temperature	Pre-arcing time-current characteristics
AC 250 V	8 A 10 A 12 A	250 A	Resistive circuit				
	PS E	15 A 20 A 25 A	100 A	PF 0.7–0.8	*1	*2	*3


<sup>\*1:</sup> After 100 cycles of 1.2  $I_N$  1 h on / 15 min off, 1.5  $I_N$  is passed through the fuse for 1 h.

<sup>\*2:</sup> A current of 1.1 I<sub>N</sub> is passed through the fuse for 1 h at a temperature of 70±2 °C.

*3:	2.1 I <sub>N</sub>	2.75 I <sub>N</sub>	4.0 I <sub>N</sub>	10 / <sub>N</sub>	
	Within 30 min	0.6 s-10 s	0.15 s–3 s	0.02 s-0.3 s	

<sup>\*4:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.





λ		<b>=</b>	( V	
	30	$\longrightarrow$		
	Lead wire diameter	φ 1.2		Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (/ <sub>N</sub> )	Rated breaking current		Temp. rise	Current carrying capacity / Endurance test	Test at elevated temperature	Pre-arcing time-current characteristics
	15 A	250 A	Resistive	-	*1	*2	*3	
AC 250 V		12 A	A A	circuit	75 K or less at 1.0 <i>l</i> <sub>N</sub>	1.0 I <sub>N</sub> until temperature stabilization occurs		Within 30 min
	PS	25 A	100 A	PF 0.7–0.8	At 1.0 I <sub>N</sub> 140 K or less at the center, 60 K or less at the contact	1.0 I <sub>N</sub> until constant temperature is obtained on each part	_	at 2.1 / <sub>N</sub>

 $<sup>^{\</sup>star}$ 1: Endurance Test: After passing 0.8  $I_N$  through the fuse for 100 h, the rated current is passed through the fuse for 1 h.


<sup>\*2:</sup> A current of 1.1 I<sub>N</sub> is passed through the fuse for 1 h at a temperature of 70±2 °C.

		•	'	_
*3:	2.1 / <sub>N</sub>	2.75 I <sub>N</sub>	4.0 I <sub>N</sub>	10 / <sub>N</sub>
	Within 30 min	0.6 s-10 s	0.15 s-3 s	0.02 s-0.3 s

<sup>\*4:</sup> This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(h) (B)	100 mA-10 A	10000 A	PF 0.7–0.8	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# **ULTSC N1**

Inrush-withstand


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics








Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 125 V	<b>(L) (D) (D)</b> • <b>(D)</b> • <b></b>	100 mA–10 A	10000 A	PF	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
AC 125 V	P\$ *2	100 MA=10 A	500 A	0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Lead wire diameter  $\phi$  0.5 (100 mA–4 A)  $\phi$  0.8 (Over 4 A–10 A)

Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current	Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(I) (I)	100 mA-10 A	10000 A PF 0.7–0.	70 K or less at 1.1 I <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


### **ULTSCR N1**

Inrush-withstand


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics







Lead wire diameter


φ 0.5 (100 mA–4 A) φ 0.8 (Over 4 A–10 A)

Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rent	Temp. rise	Current carrying capacity	Overload operation
AC 125 V	(h) <b>(B</b> •	- 100 mA–10 A	10000 A	PF	70 K or less at 1.1 <i>I</i> <sub>N</sub>	1.1 I <sub>N</sub> for 15 min or more after temperature stabilization occurs	Within 60 min at 1.35 / <sub>N</sub>
	PS *2	100 IIIA-10 A	500 A	0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 2 min at 2.0 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	<b>PS</b> *2	100 mA–5 A	500 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.


## **(A)** MSCR

Normal-acting


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics








Lead wire diameter  $\phi$  0.5 (100 mA to less than 5 A) Scale: 1/1  $\phi$  0.8 (5 A) (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	<b>PS</b> *2	100 mA–3 A	500 A	PF	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 / <sub>N</sub> until	Within 60 min at 1.35 / <sub>N</sub>
		Over 3 A–5 A	100 A	0.7–0.8		temperature is obtained on each part	Within 2 min at 2.0 <i>I</i> <sub>N</sub>


\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

3: 100 mA to less than 5 A Pb free
5 A This pro








Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	<b>PS</b> *2	100 mA-10 A	500 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

# A SCR Normal-acting RoHS-compliant Pb free

### Representative pre-arcing time-current characteristics







Lead wire diameter

 $\phi$  0.5 (100 mA to less than 5 A)  $\phi$  0.8 (5 A–10 A)


Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	<b>PS</b> *2	100 mA–5 A	500 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 / <sub>N</sub> until	Within 60 min at 1.35 / <sub>N</sub>
		Over 5 A–10 A	100 A			temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	PS *2	100 mA-20 A	500 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.


\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.


\*3: 100 mA–12 A Pb free

Over 12 A-20 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.



### Representative pre-arcing time-current characteristics






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	PS to	100 mA-15 A	500 A	PF	At 1.1 / <sub>N</sub> , 140 K or less	1.1 / <sub>N</sub> until	Within 60 min at 1.35 I <sub>N</sub>
	PS *2	Over 15 A–20 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 I <sub>N</sub>


\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

3: 100 mA-12 A Pb free







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	PS *2	100 mA-20 A	500 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.


\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.


\*3: 100 mA-12 A Pb free

Over 12 A-20 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.



### Representative pre-arcing time-current characteristics






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	DS to	100 mA-15 A	500 A	PF	At 1.1 I <sub>N</sub> , 140 K or less	1.1 / <sub>N</sub> until	Within 60 min at 1.35 / <sub>N</sub>
	<b>PS</b> *2	Over 15 A–20 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 I <sub>N</sub>


\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

3: 100 mA-12 A Pb free







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	PS *2	500 mA–30 A	500 A	PF 0.7–0.8	At 1.1 <i>I</i> <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.


\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.


\*3: 500 mA-12 A Pb free

Over 12 A-30 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.



### Representative pre-arcing time-current characteristics






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
10.405.14	PS to	500 mA-15 A	500 A	PF	At 1.1 / <sub>N</sub> , 140 K or less	1.1 / <sub>N</sub> until	Within 60 min at 1.35 / <sub>N</sub>
AC 125 V	<b>PS</b> *2	Over 15 A–30 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

3: 500 mA-12 A Pb free







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	PS *2	100 mA–5 A	500 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# **A TMSCR**

Inrush-withstand


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics







Lead wire diameter  $\phi$  0.5 (100 mA to less than 5 A) Scale: 1/1  $\phi$  0.8 (5 A) (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	PS *2	100 mA–3 A	500 A	PF	At 1.1 / <sub>N</sub> , 140 K or less	1.1 / <sub>N</sub> until constant	Within 60 min at 1.35 / <sub>N</sub>
	E 2	Over 3 A–5 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


3: 100 mA to less than 5 A Pb free 5 A This pr

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.








Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	<b>PS</b> *2	100 mA-10 A	500 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

# A TSCR Inrush-withstand RoHS-compliant Pb free

### Representative pre-arcing time-current characteristics







Lead wire diameter  $\phi$  0.5 (100 mA to less than 5 A)  $\phi$  0.8 (5 A–10 A)


Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	PS *2	100 mA–5 A	500 A	PF	At 1.1 / <sub>N</sub> , 140 K or less	1.1 / <sub>N</sub> until constant	Within 60 min at 1.35 / <sub>N</sub>
	E 2	Over 5 A–10 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	PS *2	100 mA–30 A	500 A	PF 0.7–0.8	At 1.1 <i>I</i> <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

\*3: 100 mA-12 A Pb free

Over 12 A-30 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.




Inrush-withstand


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics








Lead wire diameter  $\phi$  0.8 (100 mA-8 A)  $\phi$  1.0 (Over 8 A-15 A)  $\phi$  1.2 (Over 15 A-30 A) Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
A O 405 V	PS *2	100 mA-15 A	500 A	PF	At 1.1 / <sub>N</sub> , 140 K or less	1.1 / <sub>N</sub> until	Within 60 min at 1.35 / <sub>N</sub>
AC 125 V	,E Z	Over 15 A–30 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>


\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

3: 100 mA–12 A Pb free







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	<b>PS</b> *2	100 mA-20 A	500 A	PF 0.7–0.8	At 1.1 <i>I</i> <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

3: 100 mA-12 A Pb free

Over 12 A-20 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


## **A** TLNCR


Inrush-withstand

RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics





Lead wire diameter φ 0.8 (100 mA–8 A) φ 1.0 (Over 8 A–15 λ

φ 1.0 (Over 8 A–15 A) Scale: φ 1.2 (Over 15 A–20 A) (mn


Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
PS	PS to	100 mA–15 A	500 A	PF	At 1.1 / <sub>N</sub> , 140 K or less	1.1 / <sub>N</sub> until constant	Within 60 min at 1.35 / <sub>N</sub>
AC 125 V	PS ∗2	Over 15 A–20 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 I <sub>N</sub>


\*1: Customer-requested rated current values can be supplied from within the given range.

\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

3: 100 mA-12 A Pb free Over 12 A-20 A This pi







Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	<b>PS</b> *2	500 mA-30 A	500 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- \*3: 500 mA-12 A Pb free

Over 12 A-30 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


# (A) TLLCR


Inrush-withstand

RoHS-compliant\*3

Pb free\*3


### Representative pre-arcing time-current characteristics






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 125 V	<b>PS</b> *2	500 mA-15 A	500 A	PF	At 1.1 / <sub>N</sub> , 140 K or less	1.1 / <sub>N</sub> until	Within 60 min at 1.35 / <sub>N</sub>
AC 125 V	E 2	Over 15 A–30 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 / <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 3: 500 mA-12 A Pb free







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	PS *2	100 mA–5 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# 250V A MSCR

Normal-acting


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics







Lead wire diameter

 $\phi$  0.5 (100 mA to less than 5 A)

Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>PS</b> *2	100 mA–5 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


\*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

\*3: 100 mA to less than 5 A Pb free
5 A This pr

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>PS</b> *2	100 mA-10 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# 250V (A) SCR

Normal-acting


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics







Lead wire diameter  $\phi$  0.5 (100 mA to less than 5 A)  $\phi$  0.8 (5 A–10 A)


Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	PS *2	100 mA–10 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>PS</b> *2	100 mA-20 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 3: 100 mA-12 A Pb free

Over 12 A-20 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


### 250V (A) LCR

Normal-acting


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics







φ 1.2 (Over 15 A–20 Å)


Lead wire diameter φ 0.8 (100 mA–8 A) φ 1.0 (Over 8 A–15 A)

Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>PS</b> *2	100 mA-20 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 3: 100 mA–12 A Pb free

Over 12 A-20 A







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>PS</b> *2	100 mA-20 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 3: 100 mA-12 A Pb free
  - Over 12 A-20 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


### 250V A LNCR

Normal-acting


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics








- Lead wire diameter  $\phi$  0.8 (100 mA–8 A)
  - φ 1.0 (Over 8 A–15 A)
  - φ 1.2 (Over 15 A–20 A)
- Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>PS</b> *2	100 mA-20 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 3: 100 mA-12 A Pb free

Over 12 A-20 A







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>PS</b> *2	500 mA-30 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 I <sub>N</sub> Within 2 min at 2.0 I <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 3: 500 mA-12 A Pb free

Over 12 A–30 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


# 250V A LLCR


Normal-acting

RoHS-compliant\*3

Pb free\*3


### Representative pre-arcing time-current characteristics






Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	<b>PS</b> *2	500 mA–30 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 3: 500 mA-12 A Pb free







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	PS *2	100 mA–5 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# 250V A TMSCR

Inrush-withstand


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics







Lead wire diameter  $\phi$  0.5 (100 m.

 $\phi$  0.5 (100 mA to less than 5 A) Scale: 1/1  $\phi$  0.8 (5 A) (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1	Rated breaking current		Temp. rise	Current carrying capacity	Overload operation
AC 250 V	PS *2	100 mA–5 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


3: 100 mA to less than 5 A Pb free
5 A This pro

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	PS *2	100 mA-10 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub> Within 2 min at 2.0 / <sub>N</sub>

<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.


# 250V A TSCR

Inrush-withstand


RoHS-compliant

Pb free

### Representative pre-arcing time-current characteristics








Lead wire diameter  $\phi$  0.5 (100 mA to less than 5 A) Scale: 1/1  $\phi$  0.8 (5 A–10 A) (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	PS *2	100 mA–10 A	100 A	PF 0.7–0.8	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact	1.1 I <sub>N</sub> until constant temperature is obtained on each part	Within 60 min at 1.35 <i>I</i> <sub>N</sub> Within 2 min at 2.0 <i>I</i> <sub>N</sub>


<sup>\*1:</sup> Customer-requested rated current values can be supplied from within the given range.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

<sup>\*2:</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	P\$ *2	100 mA–5 A	500 A	PF	At 1.1 / <sub>N</sub> , 1.1 / <sub>N</sub> until 140 K or less constant	Within 60 min at 1.35 / <sub>N</sub>	
AC 250 V	<b>PS</b> *2	Over 5 A–30 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 <i>I</i> <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 100 mA-12 A Pb free

Over 12 A-30 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


### 250V A TLCR

Inrush-withstand


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics








- Lead wire diameter  $\phi$  0.8 (100 mA-8 A) φ 1.0
  - (Over 8 A-15 A)
  - φ 1.2 (Over 15 A-30 A)
- Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	PS *2	100 mA–5 A	500 A	PF	At 1.1 I <sub>N</sub> , 140 K or less	constant at 1.35	Within 60 min at 1.35 / <sub>N</sub>
AC 250 V	E 2	Over 5 A–30 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 <i>I</i> <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 100 mA-12 A

Over 12 A-30 A







Scale: 1/1 (mm)

Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	DS to	100 mA–5 A	500 A	PF	At 1.1 I <sub>N</sub> , 140 K or less at the center, 60 K or less at the contact  At 1.1 I <sub>N</sub> , constant temperature is obtained on each part	Within 60 min at 1.35 / <sub>N</sub>	
	<b>PS</b> *2	Over 5 A–20 A	100 A	0.7–0.8		is obtained	Within 2 min at 2.0 I <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 3: 100 mA-12 A Pb free

Over 12 A-20 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


### 250V A TLNCR


Inrush-withstand


RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics








- Lead wire diameter  $\phi$  0.8 (10  $\phi$  1.0 (Ov
- φ 0.8 (100 mA-8 A)
   φ 1.0 (Over 8 A-15 A)
   φ 1.2 (Over 15 A-20 A)
- Scale: 1/1 (mm)


Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	P\$ *2	100 mA–5 A	500 A	PF	At 1.1 I <sub>N</sub> , 1.1 I <sub>N</sub> until 140 K or less constant	Within 60 min at 1.35 / <sub>N</sub>	
AC 250 V	E Z	Over 5 A–20 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 <i>I</i> <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 3: 100 mA-12 A Pb free

Over 12 A-20 A T







Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
AC 250 V	PS *0	500 mA–5 A	500 A	PF	At 1.1 <i>I</i> <sub>N</sub> , 140 K or less at the center.		Within 60 min at 1.35 /N
AC 250 V	<b>PS</b> *2	Over 5 A–30 A	100 A	0.7–0.8	60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 I <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 3: 500 mA-12 A Pb free

Over 12 A-30 A This product uses high melting temperature type solder containing 85% by weight or more lead. This type of solder is exempted from the RoHS Directive.


# 250V A TLLCR


Inrush-withstand

RoHS-compliant\*3

Pb free\*3

### Representative pre-arcing time-current characteristics





Rated voltage	Certification	Rated current (I <sub>N</sub> ) *1		breaking rrent	Temp. rise	Current carrying capacity	Overload operation
40.050.1/	PS to	500 mA–5 A	500 A	PF	140 K or less constant	Within 60 min at 1.35 / <sub>N</sub>	
AC 250 V	P\$ *2	Over 5 A–30 A	100 A	0.7–0.8	at the center, 60 K or less at the contact	temperature is obtained on each part	Within 2 min at 2.0 <i>I</i> <sub>N</sub>

- \*1: Customer-requested rated current values can be supplied from within the given range.
- \*2: Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.
- 3: 500 mA-12 A Pb free

Over 12 A-30 A

Pb free

Unit: mm


### BM-SS-I-14

Fuse size: <sup>φ</sup> 5.2 mm × <sup>L</sup>20 mm AC 250 V 15 A Rating: Certification: **UL** Recognized Phenolic resin Base material:


(UL94V-0)

Surface treatment: Nickel plated









# BM-LQ-I-13

Fuse size: <sup>φ</sup> 6.35 mm × <sup>L</sup>30 mm


<sup>φ</sup> 6.35 mm × <sup>L</sup>31.8 mm

Rating: AC 250 V 30 A Certification: **UL** Recognized Base material: Phenolic resin

(UL94V-0)

Surface treatment: Tin plated





## BM-LQ-I-15


<sup>φ</sup> 10.3 mm × <sup>L</sup>38.1 mm Fuse size:

AC 250 V 30 A Rating: Certification: **UL** Recognized Base material: Phenolic resin

(UL94V-0)

Surface treatment: Nickel plated





## **△** CAUTION

- The fuseholder ratings shown above represent the maximum ratings for fuses that can be used under normal circumstances. Rated currents are based on the assumption that a fuse inserted in a fuseholder will operate at less than or equal to 1.35 times the fuseholder's rating. For all other cases, please contact your SOC representative.
- When inserting a fuse into a fuseholder, please do not force the fuse into the holder or hit the fuse. Contact failure caused by damage to the fuse or deformation of the fuseholder's clips due to impact or forcing the fuse into the holder may significantly alter the fuse's electrical characteristics and lifetime, and may lead to accidents including nuisance operations.

Pb free

Unit: mm

### H-0016-2

Fuse size: 
\$\psi 5.2 \text{ mm}\$


Rating: AC / DC 10 A


Thickness: 0.4 \text{ mm}

Material: C5191


phosphor bronze

Surface treatment: Tin plated






Referential dimensions of mounting holes




# H-0032-2


phosphor bronze

Surface treatment: Tin plated





Referential dimensions of mounting holes





# H-0014-2

Fuse size:  $^{\phi}$  6.35 mm Rating: AC / DC 15 A Thickness: 0.4 mm Material: C5191


phosphor bronze

Surface treatment: Tin plated





Referential dimensions of mounting holes



P=31 for  $^{\phi}$  6.35 ×  $^{L}$ 30 mm fuses P=33 for  $^{\phi}$  6.35 ×  $^{L}$ 31.8 mm fuses

Pb free


Unit: mm

### H-0017-2


Fuse size:  $^{\phi}$  6.35 mm Rating: AC / DC 15A Thickness: 0.5 mm Material: C5191

phosphor bronze

Surface treatment: Tin plated



Referential dimensions of mounting holes



P=34.7 for  $^{\phi}$  6.35 ×  $^{L}$ 30 mm fuses P=36.7 for  $^{\phi}$  6.35 ×  $^{L}$ 31.8 mm fuses

# H-0048-2


Fuse size:  $^{\phi}$  5.2 mm

 $^{\phi}$  6.35 mm


Rating: AC / DC 15 A
Thickness: 0.4 mm
Material: C5191

phosphor bronze

Surface treatment: Tin plated



Referential dimensions of mounting holes



P=30.6 for  $^{\phi}$  5.2 ×  $^{\text{L}}$ 20 mm fuses P=29.8 for  $^{\phi}$  6.35 ×  $^{\text{L}}$ 30 mm fuses P=31.6 for  $^{\phi}$  6.35 ×  $^{\text{L}}$ 31.8 mm fuses


## H-0084-2

Fuse size:  $^{\phi}$  10.3 mm Rating: AC / DC 30 A Thickness: 0.7 mm


Material: C5191

phosphor bronze

Surface treatment: Tin plated



Referential dimensions of mounting holes



### Technical information


### Resistance to soldering heat

- Fuses are heat-sensitive components. The soldering conditions shown below are examples based on the use of our facilities. Sufficiently evaluate and examine your company's soldering conditions as they may vary depending on such factors as available facilities, solder type, solder quantity, board size, and board materials.
- Board and solder used

Board: Glass epoxy, thickness 1.6 mm


Solder: Sn-3.0Ag-0.5Cu

■ Surface mount fuses: Reflow soldering (11CT Type / 25CT Type / 36CFA / 36CT)



Soldering can be repeated a maximum of two times under these conditions.

※ For 36CFA fuses, please ensure that the height of the fillets is not more than onethird of the entire height of the fuse.



Note: Please contact your sales representative for information concerning the MCF3.

- Sub-miniature fuses with leads (25RT Type)
  - · Wave soldering

Solder bath temp.: 260 °C or less Duration: 10 s or less

Hand soldering with soldering iron
 Soldering iron tip temp.: 380 °C or less
 Duration: 5 s or less

■ Pin terminal fuses (SMC N4)

· Wave soldering

Solder bath temp.: 265 °C or less Duration: 5 s or less

Hand soldering with soldering iron
 Soldering iron tip temp.: 350 °C or less
 Duration: 2 s or less


### ■ Cartridge fuses with leads

· Wave soldering

Preheating temp.: 80 °C–140 °C
Preheating time: 30 s–60 s
Solder bath temp.: 260 °C or less
Duration: 7 s or less

Hand soldering with soldering iron
Soldering iron tip temp.: 380 °C or less
Duration: 3 s or less

Lead wire diameter	Distance between the fuse body and the side to be soldered (L)
φ 0.5 mm φ 0.6 mm	5 mm or more
φ 0.8 mm φ 1.0 mm φ 1.2 mm	8 mm or more




Lead wire diameter	Distance between the fuse body and the side to be soldered (L)
φ 0.5 mm φ 0.6 mm φ 0.8 mm φ 1.0 mm φ 1.2 mm	5 mm or more

### Whiskers

The following tests are performed to ensure there is no whisker generation on the tin-plated parts of our products.

### ■ Temperature cycling test

After test samples are subjected to 500 cycles of temperature cycling as specified below, there shall be no whisker generation when observed using a microscope with a magnification of 40 times.



### Constant temperature and humidity test

After test samples are left at a temperature of 85 °C and an RH of 85% for 500 h, there shall be no whisker generation when observed using a microscope with a magnification of 40 times.

### Storage conditions

Prerequisite: Products shall be packaged as delivered.

Ambient temperature: -20 °C-+40 °C
Ambient humidity: 85% RH or less

Storage environment: Not exposed to corrosive gas or sea breeze.

Not exposed to direct sunlight.

Not subjected to loads which could cause deformation of the products.


Storage period: Within one year from the date on the product packaging.

# Packaging specifications

### ■ Surface mount fuses

Packag metho			Tape an	d reel packaging		Bag packaging
Packag code		F	08B4	R12A4	R24D4	В
Qty. pac	ked	20	00 pcs.	1000 pcs.	2000 pcs.	100 pcs.
	Α		4	4	8	
Dimensions	В		8	12	24	
(mm)	(mm) C 11.4 D 180		11.4	15.6	29.5	_
			178	330		
Type na	ıme	11CF 11CT 32V11CF P11CF P11CT DC35V11CT DC35VP11CF DC35VP11CF	DC86V11CT 11CFB 11CTB MCF3	25CF 25CT DC300V25CF P25CF P25CT DC35VP25CF DC35VP25CT	36CFA 36CT	Used for all fuse types

Tape and reel configuration / packing method (unit: mm)




### ■ Bag packaging for sub-miniature fuses with leads

Type name	Forming specification	Standard total qty. per box	Packaging method	
25RF	F002	2000 pcs.	100 pcs x 20 bags	
P25RF	F003	2000 μcs.	100 pcs. × 20 bags	
DC35VP25RF 25RT	F006			
P25RT	F007	1000 pcs.	100 pcs. × 10 bags	
DC35VP25RT	F116			

### ■ Bag / tape packaging for pin terminal fuses

Type name	Standard total qty. per box	Packaging method
SMC N4	1000 pcs.	Tape packaging

Tape configuration / packing method for SMC N4 (unit: mm)



### ■ Bag packaging for cartridge fuses

Fuse	Standard total quantity per box			
dimensions	O anticidenta to man	Cartridge type with leads		
(mm)	Cartridge type	Leads of $\phi$ 0.6mm or less	Leads of $\phi$ 0.8mm or greater	
<sup>ф</sup> 4 х <sup>L</sup> 9	2000 pcs. (1000 pcs. × 2 bags)	400 pcs. (100 pcs. × 4 bags)	400 pcs. (100 pcs. × 4 bags)	
φ 4.6 × L14	1000 pcs. (1000 pcs. x 1 bag)	-	200 pcs. (100 pcs. x 2 bags)	
<sup>φ</sup> 4.6 × <sup>L</sup> 16	1000 pcs. (1000 pcs. × 1 bag)	400 pcs. (100 pcs. × 4 bags)	200 pcs. (100 pcs. × 2 bags)	
<sup>φ</sup> 5.2 × <sup>L</sup> 20	1000 pcs. (1000 pcs. x 1 bag)	400 pcs. (100 pcs. x 4 bags)	200 pcs. (100 pcs. x 2 bags)	
<sup>φ</sup> 6.35 × <sup>L</sup> 15.9	500 pcs. (500 pcs. x 1 bag)	-	200 pcs. (100 pcs. x 2 bags)	
<sup>φ</sup> 6.35 × <sup>L</sup> 20	-	-	100 pcs. (100 pcs. × 1 bag)	
<sup>φ</sup> 6.35 × <sup>L</sup> 25.4	500 pcs. (500 pcs. x 1 bag)	-	100 pcs. (100 pcs. x 1 bag)	
<sup>φ</sup> 6.35 × <sup>L</sup> 30	500 pcs. (500 pcs. × 1 bag)	-	100 pcs. (100 pcs. × 1 bag)	
<sup>φ</sup> 6.35 × <sup>L</sup> 31.8	400 pcs. (400 pcs. x 1 bag)	-	100 pcs. (100 pcs. x 1 bag)	
<sup>φ</sup> 7.14 × <sup>L</sup> 31.8	300 pcs. (300 pcs. × 1 bag)	-	-	
<sup>φ</sup> 10.3 × <sup>L</sup> 38.1	100 pcs. (100 pcs. x 1 bag)	-	50 pcs. (50 pcs. x 1 bag)	

Please contact your sales reprentative for product packaging specifications not listed in this catalog.

# Forming specifications


Please contact your sales representative for forming specifications not listed below and for questions regarding dimensional tolerances.

### ■ Cartridge fuses with leads (unit: mm)


The D dimensions in parentheses are for reference purposes only, and are not intended to infer any guaranteed values.

Fig. No.	Fuse dimensions	Lead wire Forming No.		Dimensions			
Fig. No.	ruse dimensions	diameter	Forming No.	Α	В	С	D
	<sup>φ</sup> 4 × <sup>L</sup> 9	0.8	F451	5.2	10	9	(10)
	<sup>φ</sup> 4.6 × <sup>L</sup> 16	0.8	F051	5.2	10	16	(17)
	<sup> </sup>	0.8	F013	5	9.5	20	(21)
* 1		1.0	F057	5	8.6	20	(21.4)
_ ^ I	<sup>φ</sup> 6.35 × <sup>L</sup> 30	1.0	F916	5	9.7	30	(32.2)
	<sup>φ</sup> 6.35 × <sup>∟</sup> 31.8	1.0	F019	5	40	31.8	(33)
		1.2	F021	5	9	31.8	(33)
	0.8	F918	5	9	31.8	(33)	
* 2	<sup>⋄</sup> 6.35 × <sup>∟</sup> 30	1.2	F915	5	9.7	30	(32.2)
* 3	<sup>ф</sup> 6.35 х <sup>L</sup> 30	1.2	F502	5	9.7	30	(25)
	<sup>⋄</sup> 4.6 × <sup>∟</sup> 14	0.8	F024	5	10	14	(15)
4	<sup>φ</sup> 4.6 × <sup>L</sup> 16	0.8	F025	5	10	16	(17)
* 4	<sup>φ</sup> 5.2 × <sup>L</sup> 20	0.8	F026	5	10	20	(21)
		1.0	F036	5	10	20	(21)







\* 2




\* 3




\* 4




### ■ 25RT Type fuses (unit: mm, lead wire diameter: $\phi$ 0.8mm)






Forming No. F003


12.5




Forming No. F006



Forming No. F007



Forming No. F116




### ■ Lead wire forming

When forming by hand

○ Correct



When forming with forming dies



× Incorrect







When forming lead wires, always secure the area between the fuse body and the part of the lead wire to be formed as shown in the figure above. Make sure not to put any stress on the area connecting the fuse body and the lead wire.

### Fuse selection process

### Fuse selection process

Properly selected fuses prevent accidents by breaking abnormal currents when they flow through electric circuits. Improper selection, however, can result in nuisance operations, continued flow of abnormal currents, generation of smoke and/or fire, and other dangers.

### Safety precautions when selecting fuses

■ What is the voltage of the circuit the fuse will be used in?

### Make sure to select a fuse that has a rated voltage higher than the voltage of the circuit.

The rated voltage of a fuse is the maximum voltage at which the fuse can safely interrupt an abnormal current. If the voltage of the circuit is higher than the fuse's rated voltage, there is a danger the fuse may be destroyed as shown below. Please exercise caution.



Example of a breaking test where the circuit voltage is higher than the rated voltage of the fuse

■ Will the fuse be used in an AC circuit or a DC circuit?

### Only select DC rated fuses for DC circuits, and AC rated fuses for AC circuits.

For AC circuits, there is a tendency for arc discharges to be extinguished when the power supply voltage goes to zero as shown in Figure 1 below. Caution should be exercised regarding use of DC circuits as DC voltage does not go to zero, and therefore there is the risk that an arc discharge may not be extinguished which may result in destruction of the fuse.

Therefore, due to the difference in circuit characteristics for AC and DC circuits, mistakenly using an AC fuse in a DC circuit or a DC fuse in an AC circuit may cause an accident.




Figure 1 - Fuse operation waveforms and showing the difference between AC and DC circuits (actual waveforms may differ from the above)

■ What is the power factor / time constant of the circuit in which the fuse is to be installed?


The amount of the inductance of the circuit relates to the magnitude of the power factor or the time constant. When interrupting an abnormal current in a circuit with a large inductance, an arc voltage greater than that of the power supply may occur, and the fuse may be unable to safely break the current. The larger the inductance, the greater the arc energy generated at the fuse. The fuse is destroyed if it cannot withstand the arc energy.

When selecting fuses, please confirm that the fuse you have selected can safety clear abnormal currents in the equipment in which it is to be used.

- How will the fuse be mounted?
  - (1) Mounting directly to a wiring circuit board a) Surface mount type



b) Terminals passed through holes in a wiring circuit board (pin terminals, lead terminals, and others)



(2) Mounting a fuse in a fuseholder (or clips)



(3) Directly bolted to a circuit



Please contact us for development of custom-designed fuses based on your shape and dimensional requirements.

■ How large current will be passed through the circuit the fuse will be used in?

A rated current is defined for each fuse, and this value is marked on it. Understanding the following circuit currents (including their waveforms) is important for selecting the appropriate rated current and rated breaking current for a fuse in order to prevent nuisance operations and ensure the fuse is able to interrupt abnormal currents.

- · Steady-state current
- · Inrush current
- · Abnormal current
- \*1 "Rated breaking capacity" is used in IEC 60127 (Miniature fuses) series, "interrupting rating" in the UL/CSA 248 series (Low-voltage fuses), and "rated breaking capacity" in JIS C 6575 (Miniature fuses) series, but all of these refer to the rated breaking current.

### (1) Evaluation of a steady-state current

In order to avoid nuisance operation over long-term use, please select a fuse which has pre-arcing time-current characteristics <sup>2</sup> such that the fusing current is sufficiently larger than the steady-state current (root mean squared value) of the actual circuit in which the fuse will be installed. Figure 2 shows an example of the necessary difference (margin) between fusing current and actual circuit current.




Figure 2 - Fuse selection example for a steady-state current

### \*2 Pre-arcing time-current characteristics:

As shown in Figure 3, pre-arcing time-current characteristics are created from the average pre-arcing time values for a number of constant currents. These are not guarantees of a fuse's characteristics. This current is a current that would flow in the circuit if a fuse were replaced by a link of negligible impedance (prospective current).

Prospective current	Average pre-arcing time
Current	pre-arcing time
30 A	0.018 s
20 A	0.058 s
10A	0.33 s
7 A	0.91 s
5 A	3.9 s
4.5 A	82 s




Figure 3 - Example of how to plot pre-arcing time-current characteristics

### (2) Evaluation of an inrush current

Generally it is not possible to evaluate inrush currents with pre-arcing time-current characteristics, since the peak values of inrush currents change dramatically with time. However, it is possible to evaluate the occurrence of nuisance operations by comparing the circuit's Joule integral ( $I_m^2t$ , the integral of the square of the instantaneous current passed through the circuit over a certain time interval) with the pre-arcing Joule integral of the fuse ( $I_f^2t$ ) in the short-time range where heat release from fuse-element to fuse body or fuse-terminations is not large.

### **Evaluation process**

- Repeatedly measure the current waveform of the circuit from when the equipment is powered on (inrush current) to the steady-state current.
- ii) Discharge the remaining electric charge in the circuit's capacitor and measure the current waveform. If there is a component like a thermistor with a resistance that changes depending on the temperature, measure the current waveform at the minimum resistance.
- iii) Based on the measured current waveform, calculate the circuit's Joule integral  $(I_{\rm m}^2 t)$  for each time. For example, the circuit's Joule integral is calculated as follows when you have the Joule integral for 0.01 s and the sampling interval  $\Delta$  t is equal to 0.001 s. Note that the instantaneous value of the current that flows through the circuit is represented by  $i_{\rm m}(t)$ . In actual practice, an even smaller sampling interval is used. A larger value was selected to explain the process. 0.01 s divided by 0.001 s is equal to 10. Therefore:

$$I_m^2 t \mid_{t=0.01} = \int_{t=0}^{0.01} [i_m(t)]^2 dt \approx \sum_{k=1}^{10} \{ [i_m(\Delta t \cdot k)]^2 \times \Delta t \}$$

- iv) Calculate the Joule integral for each time and plot the values on a graph as in Figure 4.
- v) As in Figure 5, plot the graph with the circuit's maximum Joule integral and the fuse's pre-arcing Joule integral as functions of the time. In order to prevent nuisance operation, the relationship of maximum circuit Joule integral ≤ fuse pre-arcing Joule integral is always necessary, and in order to prevent nuisance operations caused by aging, it is necessary to select fuses with sufficient margin (for example, the shaded region in Figure 5). As the necessary margin differs depending on the usage conditions, it is necessary to perform evaluations in the actual equipment the fuse will be used in.

### (3) Evaluation of an abnormal current

Measure the maximum possible abnormal current and select a fuse with a rated breaking current that can interrupt that abnormal current. Additionally, the minimum possible abnormal current should also be measured. In the comparatively short-time region, the fuse's Joule integral shall be less than or equal to the Joule integral of the circuit when the minimum abnormal current flows through it. In the comparatively long-time region, the fuse's minimum pre-arcing current shall be less than or equal to the abnormal current. The judgement whether or not these two relationships are fulfilled, depending upon the protection conditions at what point and over what time the abnormal current is required to be interrupted, can be difficult in most cases. Therefore it is both necessary and important to confirm whether the fuse can safely interrupt the abnormal current in the actual application.




Figure 5 - Fuse selection example for an inrush current

Before final fuse selection, always test the proposed fuse in your actual equipment to ensure that the fuse satisfies all your operational and safety requirements. Please contact your local SOC sales representative for help in selecting fuses.

#### Explanation of rated current

The requirements stipulated by each standard differ even among fuses with the same rated current, and each standard specifies pre-arcing (operating) times for multiples of the rated current ( $I_N$ ). In other words, pre-arcing time-current characteristics differ depending on the standard even when the rated current is the same.




Figure 6 - Examples of pre-arcing time-current characteristics for the same rated current based on different standards

On July 1, 2013, the Ministry of Economy, Trade and Industry (hereinafter called "METI") Order establishing technical requirements for electrical appliances and materials was completely revised (with implementation from January 1, 2014) in order to change detailed specification requirements to safety performance requirements. The third table appended to the order prior to the revision (hereinafter called the "prior technical requirements") is, at the current moment, approved to be used as one of the criteria for safety performance requirements for fuses according to the interpretation of the Ministerial Order. Specifications stipulated in the prior technical requirements for miniature fuses have been partially modified and incorporated into the JIS C 6575 (Miniature fuses) series step by step, taking into consideration consistency with the IEC 60127 series.

Within the JIS C 6575 series, specifications in the standard sheets containing the letter "J" are based on the prior technical requirements, while those with only Arabic numerals are based on the IEC standard. Revision of JIS standards can take a long time, and new versions may be delayed in some cases.

Tables 2-1, 2-2, and 2-3 show examples of minimum fusing currents and pre-arcing/operating times stipulated by different standards.

Table 2-1: UL 248-14 (CSA C22.2 No. 248.14) Supplemental fuses with rated currents

	Operating time <sup>*3</sup> & current	Current carrying capacity	
Microfuse*4	Within 1 min at 2 I <sub>N</sub>	Within 1 min at 2 / <sub>N</sub> Within 60 min at 1.35 / <sub>N</sub> /N until temperature stabilization	
All other fuses	Within 60 min at 1.35 $I_{\rm N}$		

<sup>\*3</sup> An operating time is the sum of a pre-arcing time and an arcing time. In the low-current region, pre-arcing times are much longer than arcing times, making operating times and pre-arcing times roughly equivalent in this region.

Table 2-2: JIS C 6575-2 (Cartridge fuses) Standard sheet J1

Class	Pre-arcing time & current	Current carrying capacity
А	Within 60 min at 1.35 / <sub>N</sub>	1.1 I <sub>N</sub> for at least 60 min
В	Within 60 min at 1.6 / <sub>N</sub>	1.3 I <sub>N</sub> for at least 60 min
Special	Within the manufacturer's indicated time at the indicated current	/N for at least 60 min

<sup>\*4</sup> Each of the main dimensions (total length, width, height, and diameter) must be less than or equal to 10 mm, not including lead or in terminals.

Table 2-3: IEC 60127 series

Standard and standard sheet number	Pre-arcing time & current	Current carrying capacity at endurance test end
IEC 60127-2 <sup>*5</sup> SS 1, 2, 5, 7, 9, 10	Within 30 min at 2.1 I <sub>N</sub>	
SS 3, 6	Within 2 min at 2.1 I <sub>N</sub>	1.5 I <sub>N</sub> for 60 min for I <sub>N</sub> of 6.3 A or less 1.5 I <sub>N</sub> for 30 min for I <sub>N</sub> greater than 6.3 A
SS 8	Within 2 min at 2.1 $I_N$ (however, for $I_N$ greater than or equal to 8 A, the pre-arcing time shall be within 10 min)	
SS 4	Within 20 s at 2 I <sub>N</sub>	1.15 <i>I</i> <sub>N</sub> for 60 min
IEC 60127-3 <sup>*6</sup> SS 1, 2	Within 5 s at 2 I <sub>N</sub>	I <sub>N</sub> value for 4 h
SS 3	Within 30 min at 2.1 / <sub>N</sub>	4.5.1.5a. CO main
SS 4	Within 2 min at 2.1 $I_N$ (however, for $I_N$ greater than 6.3 A, the pre-arcing time shall be within 5 min)	1.5 <i>I</i> <sub>N</sub> for 60 min
IEC 60127-4 <sup>*7</sup> SS 1, 2	Within 2 min at 2 I <sub>N</sub>	1.25 <i>I</i> <sub>N</sub> for 60 min
IEC 60127-7 <sup>*8</sup> SS 1	Within the manufacturer's indicated time, but not more than 60 min at 2 $I_{\rm N}$ or 2.1 $I_{\rm N}$	The manufacturer's indicated current for 60 min

- \*5 Cartridge fuse-links (fuses are referred to as "fuse-links" in the IEC standard)
- \*6 Sub-miniature fuse-links, with no principal dimension (length, width, height, and diameter) exceeding 10 mm
- \*7 Universal modular fuse-links
- \*8 Miniature fuse-links for special applications

#### ■ Time-current characteristics

As per Figure 7, it is possible to design fuses having the same rated current, but with differing pre-arcing time-current characteristics. Please consult with SOC sales representatives when it is necessary to prevent nuisance operation due to an inrush current, or when an abnormal current should be interrupted more quickly.




Figure 7 - Imaginal figure to explain differences in pre-arcing-time current characteristics for the same rated current

#### Rated breaking current

The rated breaking current is the upper limit value of prospective current that a fuse is capable of safely breaking under test conditions defined in a standard. Generally, breaking capacity tests are conducted using a circuit with a voltage 1–1.05 times the rated voltage of the fuse. As shown in Table 4-1 and 4-2, values of the rated breaking current differ depending on the standard. The lower limit value of current which a fuse can safely break is referred to as the minimum breaking current. For fuses with a minimum breaking current that is greater than the minimum fusing current, care should be taken as it cannot protect against overload currents between the minimum fusing current and minimum breaking current.

Table 4-1: UL 248-14 (CSA C22.2 No. 248.14) Supplemental fuses

	Rated breakin	g current	Power factor (lagging)
Microfuses	50 A or n	nore	0.95–1
	As a rule, the rated breaking cut for rated voltages greater than however, a fuse rated AC 250 \ and this rating shall be 10,000 \text{/} following at AC 250 \ V	or equal to AC 125 V; / may have a dual rating	
	<i>I</i> <sub>N</sub> ≦ 1 A	35 A	0.7–0.8
	1.1 A ≦ <i>I</i> N ≦ 3.5 A	100 A	
All other fuses	$3.6 \text{ A} \le I_{\text{N}} \le 10 \text{ A}$	200 A	
	10.1 A ≦ I <sub>N</sub> ≦ 15 A	750 A	
	15.1 A ≤ I <sub>N</sub> ≤ 30 A	1,500 A	
	50,000 A or 1	00,000 A	0.2 or less
	Equal to or less than 10,000 A i less than AC 125 V	s permitted for ratings	0.85–1

Table 4-2: Breaking capacities stipulated in the JIS and IEC standards (excluding fuses for special applications according to IEC 60127-7\*9)

Standard number	Standard sheet number	Rate	d breaking current	Power factor (lagging)
		Low-breaking capacity	100A	
JIS C 6575-2	SS J1	Intermediate- breaking capacity	300 A or 500 A	0.7–0.8
		High-breaking capacity	1,500 A or 2,500 A	
JIS C 6575-3	SS J1, J2	Low-breaking capacity	100 A	- 0.7–0.8
313 0 0373-3	00 01, 02	Intermediate- breaking capacity	300 A or 500 A	0.7-0.0
		Low-breaking capacity	100 A	
JIS C 6575-4	SS J1, J2	Intermediate- breaking capacity	300 A or 500 A	0.7–0.8
		High-breaking capacity	1,000 A or 1,500 A	
	SS 1, 5, 9, 10	High-breaking capacity	1,500 A	0.7–0.8
IEC 60127-2	SS 2, 3, 4	Low-breaking capacity	35 A or 10 I <sub>N</sub> , whichever is greater	Resistive circuit
120 00 127-2	SS 6	Enhanced	150 A	Resistive circuit
	SS 7, 8	breaking capacity	200 A	0.95–1
IEC 60127-3	SS 1, 2	Low-breaking	50 A	Greater than 0.95,
120 00 127-3	SS 3, 4	capacity	35 A or 10 I <sub>N,</sub> whichever is greater	less than or equal to 1
		High-breaking capacity	1,500 A	0.7–0.8
	SS 1, 2 (Rated voltage 250 V)	Intermediate- breaking capacity	500 A	0.8–0.9
IEC 60127-4		Low-breaking capacity	100 A	
	SS 1, 2 (Rate voltage 125 V)	Low-breaking capacity	50 A or 10 I <sub>N,</sub> whichever is greater	Greater than 0.95, less than or equal to 1
	SS 1, 2	Low-breaking	35 A or 10 I <sub>N</sub>	Ticos triair or equal to 1
	(Rated voltage 63 V or less)	capacity	whichever is greater	

For the rated breaking current, manufacturers can specify any value equal to or less than 50,000 A but equal to or greater than 10 times the rated current.

#### What is the fuse's ambient temperature?

A fuse will operate when the temperature of the fuse-element exceeds the melting point of the metal it is comprised of, due to Joule heating caused by overcurrents. The temperature of the fuse-element is strongly influenced by heat dissipation. As can be imagined from Figure 8, heat dissipation differs according to the heat conductivity of the surrounding components, including fuse clips, fuseholders, wiring, and the circuit board, as well as the ambient temperature conditions. The pre-arcing time-current characteristics, for example, vary depending on ambient temperature conditions as in Figure 9. Therefore it is essential for final equipment testing to be conducted with the end application subjected to actual mechanical, electrical, and ambient conditions in order to assure achievement of satisfactory results and desired reliability. The effect of ambient temperature on pre-arcing time-current characteristics can be confirmed by temperature re-rating as shown in Figure 10. Please contact your SOC sales representative for temperature re-rating information.




Figure 8 - Image showing heat transfer for a glass cartridge fuse




Figure 9 - Example of the effects of a changing ambient temperature on pre-arcing time-current characteristics




Figure 10 - Example of re-rating of rated current by ambient temperature

## Certifications

Certification is the process by which an independent third-party, through a product and factory inspection, verifies whether an industrial product's functionality or quality satisfies certain standards. For fuses, products which have obtained certification have the certification mark displayed on the actual product or the packaging.

We have concluded separate contracts with four certification organizations: UL (Underwriters Laboratories Inc.), CSA (Canadian Standards Association), SEMKO (Intertek Semko AB), and BSI (British Standards Insitutuion), and we have received permission to use their certification marks for certain fuses.

Fuses which display a certification mark in accordance with these contracts are called "certified fuses." Generally, certification bodies inspect and run tests on the fuse and verify whether it meets certain conditions. In order to ensure future compliance, factory inspections and sample tests are conducted.

The PSE mark differs from certification marks. This mark shall be displayed on fuses, which are regulated by the Electrical Appliance and Material Safety Act as electrical products. Below is an explanation of the mark displayed on the product and packaging.

## **PSE Mark**

The PSE Mark is based on the Electrical Appliance and Material Safety Law (EAMSL) of Japan. As per the EAMSL, parts of electrical facilities for general use, or machines, appliances, or materials for use in connection thereto, stipulated by the Order for Enforcement of the EAMSL, are regulated as electrical appliances and materials.

In regard to fuses, those rated AC 100 V to 300 V and 1 A to 200 A are categorized as electrical appliances and materials according to this order. As a Notifying Supplier for enclosed fuses, SOC notifies the METI of the type classifications, specified in the Regulation for Enforcement of the EAMSL, for enclosed fuses that we manufacture in accordance with the EAMSL.

The fuses SOC manufactures which are rated AC 100 V to 300 V and with rated currents equal to or greater than 1 A (hereinafter called "the relevant fuses") are categorized as specific electrical appliances and materials per the above order. Unless the relevant fuses satisfy the requirements provided in the EAMSL, they cannot, as a general rule, be sold in Japan.

One of these requirements is that the relevant fuses must be marked as stipulated in the Enforcement Regulations.

In order to bear the markings, the relevant fuses are required to be in compliance with the technical requirements stipulated in the METI Order establishing technical requirements for electrical appliances and materials. Sample fuses that fall within each type classification as the relevant fuses must be tested by a test house registered with the METI in order to receive at least one valid conformity certificate for each type classification.

SOC applies to the Japan Electrical Safety & Environment Technology Laboratories (JET) for conformity certificates (which are valid for seven years from the date of issue) such that at least one certificate is valid for each type classification of the relevant fuses that SOC sells to the Japanese market.

In principle, packing labels for the relevant fuses for the Japanese market are marked with the PSE Mark and Jet, the abbreviated name of the Japan Electrical Safety & Environment Technology Laboratories, as well as our trademark "SOC" and the fuse's electrical ratings. The position of Jet is beneath or on the right side of . The relevant fuses themselves are also marked with "SOC," and if there is sufficient space, with .



Example of PSE Mark

Fuses which have been manufactured entirely for export to countries outside of Japan, however, are not marked with  $\stackrel{\circ}{\sim}$  **JET**, nor are their packaging.

### Certification Marks for North America

The following is an explanation of the markings shown on products, and/or packaging, which have received either UL (Underwriters Laboratories Inc.) or CSA (Canadian Standards Association) product certification services.

#### ■ UL Listing Mark

This is a mark based on the UL Listing and Follow-Up Services. UL tests product samples (fuses) to check conformity with the applicable UL standards. After a set of reports are issued by UL, authorization to use the UL Listing Mark is provided based on the conditions listed in the reports.

In order to ensure that all future fuses continue to be in conformance to the requirements described in the reports, UL conducts quarterly on-site inspections and sampling tests as part of their Follow-Up Services.

The standard with which SOC fuses must conform is UL 248-14: Supplemental Fuses. This standard is Part 14 of UL 248 Low-Voltage Fuses, which consists of 20 parts. The UL 248 standards are coordinated among the United States, Canada, and Mexico. The requirements of the UL and CSA standards are the same for Part 14 as listed below:

ANSI / UL 248-14 = CAN / CSA C22.2 No.248.14

In 1992, the Standards Council of Canada (SCC) granted UL Canadian Certification Organization and Testing Organization status providing services for Canada. This enabled UL to begin conducting tests and issuing certifications for Canada.

SOC began requesting certifications for both Canada and the USA when we apply for Listing Services for a new product. As the requirements of both the UL and CSA standards are the same, use of the C-UL US Listing Mark is accepted in the issued reports without the need for additional testing, with a description stating that, in addition to UL 248-14, the requirements of CSA C22.2 No. 248.14 have also been evaluated.





When space permits, the UL Listing Mark is marked on our applicable fuses. For cartridge fuses, the mark is die-stamped on the side of one of the end-caps. Along with either the UL Listing Mark or the C-UL Listing Mark, "Listed," "360C" (the control number assigned to SOC), and the product identity ("SUPPLEMENTAL FUSE," "MISCELLANEOUS FUSE," "MINIATURE FUSE," or "MICRO-FUSE") are also printed on the packaging.

#### UL Recognized Component Mark

This mark is based on the UL Component Recognition and Follow-Up Services. In the same way as the UL Listing and Follow-Up Service, UL tests product samples (either fuses or fuseholders) in order to issue a set of reports and authorize the use of the UL Recognized Component Mark under the conditions specified in the reports. Additionally, in order to confirm that the fuses produced afterward continue to be in conformance with the requirements described in the reports, UL conducts quarterly onsite inspections and sampling tests as part of their Follow-Up Services.



Although the Listing Service requires that the fuses conform to the UL standard, the Component Recognition Service does not necessarily require this as it is possible to change a portion of the UL standard requirements. For example, although 5 x 20 mm cartridge fuses based on IEC 60127-2 do not meet the time-current characteristics of the UL standards, SOC can apply for the Component Recognition Service for these fuses according to the characteristics and breaking capacities stipulated by the IEC standard. Applications for this service can also be made for fuses having only the DC rating. SOC applies for these services for some of our fuseholders as well.



Recognized Components which have undergone the Component Recognition and Follow-Up Services are components that are used in equipment. UL evaluates whether the fuse or fuseholder is appropriate for use in the end-equipment, and if it is a fuse, whether the fuse can appropriately protect the equipment.

As with the Listing and Follow-Up Services, when certification for both the USA and Canada is applied for under the Component Recognition and Follow-Up Services, use of the C-UL US Recognized Component Mark is permitted.

In most cases, we mark the Recognized Component Mark or the C-UL US Recognized Component Mark on the packaging instead of on the product itself.

#### CSA Mark

This mark is based on the CSA Certification Service, which is essentially the same as the UL Listing and Follow-Up Services. Use of this mark is authorized under the conditions stated in the reports issued under this service. On-site inspections and sampling tests are conducted during factory audits.




When space permits, this mark is placed on our fuses. For cartridge fuses, the mark is die-stamped on the side of one of the end-caps. This mark is also printed on our packaging.

### ■ CSA Component Acceptance Mark

instead of on the product itself.

This mark is based on the CSA Component Acceptance Service, which is fundamentally the same as the UL Component Recognition and Follow-Up Services. For the CSA Component Acceptance Mark, a triangle is added to the CSA Mark. On-site inspections and sampling tests are conducted during factory audits for this mark as well.





## Certification Marks for Europe

#### ■ S Mark

This mark is based on the certification service provided by Intertek Semko AB (SEMKO).

SEMKO tests product samples in accordance with the requirements of the applicable EN standards, and issues certificates and permits use of the S Mark for products which can be confirmed as meeting the requirements.

When SEMKO considers that a product conforms to the minimum safety requirements, usage of the S Mark is permitted for the product tested under the conditions modified from EN standards after the issuance of a certificate.

Unlike UL or CSA, the same S Mark is permitted to be used for products which satisfy the minimum safety requirements regardless of conformity to the EN standard.

The S Mark is indicated on the packaging for our fuses which have received this certification. For marking on the fuse itself, however, use of the S mark without "Intertek" is accepted due to the limited space on the fuse.





S Mark without "Intertek"

### ■ Kitemark

This mark is based on the Kitemark certificate issued by the British Standards Institution (BSI). BSI issues the Kitemark certificate in those cases where product samples are confirmed by testing to meet the relevant British Standards (BS EN 60127-2), and additionally where the quality system for its production conforms to BS EN ISO 9001. BSI grants the right to use the Kitemark based on the Kitemark certificate. At least once a year on-site inspections and sampling tests are conducted for continued use of the mark. One of end-caps of the certified fuses is marked with the Kitemark.



## **Quality System**

SOC has obtained certification of our quality management system for designing and manufacturing fuses.

Location	Certification agency	Certification
Tochigi Factory	DNV *1	Standard ISO 9001: 2015
	DNV *2	Standard IATF 16949: 2016 (only for vehicles)
Akita Factory	BSI *3	Standard ISO 9001: 2015

<sup>\*1</sup> DNV Business Assurance UK Limited

<sup>&</sup>lt;sup>\*2</sup>DNV Business Assurance USA Inc.

<sup>&</sup>lt;sup>\*3</sup>British Standards Institution

## Search by certification

PS *	(l) or <b>91</b>	or (I)	(\$)	♡	Shape	Dimensions (mm)	Rated voltage	Characteristic	Type name	Rated current	Page
•	•	•	•	•	Cartridge type				ET	50 mA-6.3 A	58
•	•	•	•	•	Cartriage type	<sup>¢</sup> 5.2 × <sup>∟</sup> 20		Time-lag	HT N5	1 A-10 A	62
•	•	•	•	•	Cartridge type with leads				HTR N5	1 A–10 A	63
•	•	•	•		Surface mount type	<sup>w</sup> 3.6 × <sup>H</sup> 3.6 × <sup>L</sup> 17	40.050.1/	Inrush-withstand	36CT	1 A–6.3 A	34
•	•	•	•		Cartridge type	<sup>6</sup> 6.35 × <sup>1</sup> 30	AC 250 V		TLC N4	8 A–25 A	106
•	•	•	•		ournings type	<sup>⋄</sup> 5.2 × <sup>∟</sup> 20		Time-lag	ET6	1 A–6.3 A	59
•	•	•	•		Cartridge type	<sup>¢</sup> 6.35 × <sup>∟</sup> 30		Inrush-withstand	TLCR N4	8 A–25 A	107
•	•	•	•		with leads	<sup>¢</sup> 5.2 × <sup>∟</sup> 20		Time-lag	ET6R	1 A-6.3 A	60
•	•	•	•		Pin terminal type	<sup>W</sup> 4 × <sup>H</sup> 7.7 × <sup>L</sup> 8.4		Inrush-withstand	SMC N4	4 A	35
•	•	•			Surface mount	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	AC 125 V	Quick-acting	25CF	Over 4 A–6.3 A	24
•	•	•			type	2.51 ~ 2.51 ~ 0.1	AC 123 V	Inrush-withstand	25CT	Over 3.15 A–5 A	25
•	•	•				<sup>∅</sup> 10.3 × <sup>∟</sup> 38.1		Inrush-withstand	KST2 N1	6.3 A-30 A	70
•	•	•				10.5 ^ 36.1		IIII usi i-witi istariu	SKM10 N1	1 A–25 A	90
•	•	•					AC 250 V	Normal-acting	SS2 N1	50 mA-5 A	94
•	•	•					AC 230 V	Normal-acting	SS6 N1	Over 5 A–8 A	97
•	•	•						Inrush-withstand	CES14 N1	100 mA-10 A	67
•	•	•				<sup>¢</sup> 6.35 × <sup>∟</sup> 31.8		IIII usi i-witi istailu	ST4 N1	100 mA-8 A	99
•	•	•			Cartridge type			Normal-acting	SS6 N1	Over 8 A–15 A	97
•	•	•			Cartridge type		AC 125 V	Inrush-withstand	CES6 N1	100 mA-15 A	65
•	•	•						IIII usii-wili islanu	ST6 N1	100 mA-15 A	103
•	•	•						Normal-acting	MQ4 N1	62 mA-3 A	74
•	•	•					AC 250 V	Inrush-withstand	MT4 N1	100 mA-3.5 A	80
•	•	•				<sup> </sup>		IIII usi i-witi istailu	MT4 N1D	100 mA-3.5 A	83
•	•	•					AC 125 V	Normal-acting	MQ2 N1	62 mA-10 A	72
•	•	•					AC 123 V	Inrush-withstand	ULTSC N1	100 mA-10 A	108
•	•	•						Normal-acting	SS1 N1	50 mA-5 A	93
•	•	•					AC 250 V	Normal-acting	SS5 N1	Over 5 A–8 A	96
•	•	•					AO 250 V	Inrush-withstand	CES15 N1	100 mA-25 A	69
•	•	•				<sup>¢</sup> 6.35 × <sup>∟</sup> 31.8		IIII usi i-witi istanu	ST3 N1	100 mA-8 A	98
•	•	•						Normal-acting	SS5 N1	Over 8 A–15 A	96
•	•	•					AC 125 V		CES7 N1	100 mA-15 A	66
•	•	•			Cartridge type with leads			Inrush-withstand	ST5 N1	100 mA-15 A	101
•	•	•				<sup>φ</sup> 6.35 × <sup>L</sup> 20			250VTMCR N1	1 A-20 A	64
•	•	•					AC 250 V	Normal-acting	MQ3 N1	62 mA-3 A	73
•	•	•					7.0 200 V	Inrush-withstand	MT3 N1	100 mA-3.5 A	75
•	•	•				<sup>¢</sup> 5.2 × <sup>∟</sup> 20		muon willistallu	MT3 N1D	100 mA-3.5 A	78
•	•	•					AC 125 V	Normal-acting	MQ1 N1	62 mA-10 A	71
•	•	•					7.5 120 V	Inrush-withstand	ULTSCR N1	100 mA-10 A	109
•	•	•			Bolted connection type	<sup>φ</sup> 10 × <sup>L</sup> 32	AC 250 V	-	AC250VBL1030C	40 A–60 A	52
	•	•	•			<sup>¢</sup> 6.35 × <sup>∟</sup> 31.8	AC 400 V	Incustration of the second	SHV14	10 A-20 A	40
	•	•	•		1		DC 400 V	Inrush-withstand	SHV12	1 A-6.3 A	39
	•	•	•		0	<sup>φ</sup> 5.2 × <sup>∟</sup> 20		Out-to-	HQ N7	400 mA-6.3 A	61
	•		•	•	Cartridge type		40.0501	Quick-acting	EQ	80 mA-6.3 A	57
•	•					<sup>¢</sup> 6.35 × <sup>∟</sup> 31.8	AC 250 V	In march 200 ct at	CES14 N2	Over 10 A-15 A	68
•	•					<sup>¢</sup> 5.2 × <sup>∟</sup> 20		Inrush-withstand	MT4 N2	Over 3.5 A–15 A	81

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

PS *	(a)	( ) c	(2)	\$ Shape	Dimensions (mm)	Rated voltage	Characteristic	Type name	Rated current	Page
•	•			Cartridge type				MT4 N2D	Over 3.5 A-15 A	84
•	•			Cartridge type	<sup>¢</sup> 5.2 × <sup>∟</sup> 20	AC 250 V	Inrush-withstand	MT3 N2	Over 3.5 A-15 A	76
•	•			with leads				MT3 N2D	Over 3.5 A-15 A	79
•			•	Sub-miniature type with leads	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 9	AC 125 V	Quick-acting	25RF	200 mA-5 A	28
	•	•			<sup>W</sup> 3.6 × <sup>H</sup> 3.6 × <sup>L</sup> 17	AC 250 V DC 300 V	Inrush-withstand	36CT	1 A-6.3 A	34
				•	W H	DC 600 V		_	63 mA-3.15 A	
	•	•			<sup>w</sup> 3.6 × <sup>н</sup> 3.6 × <sup>∟</sup> 11	DC 425 V		36CFA	4 A	35
	•	•				DC 300 V		DC300V25CF	63 mA-2 A	25
						AC 250 V				
						DC 150 V	Quick-acting		63 mA–4 A	
	•	•				AC 125 V		25CF		24
						DC 150 V			Over 4 A–15 A	
					<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	DC 86 V			63 mA-5 A	-
					2.0. 2.0. 0	AC 250 V			00 1121 071	
						DC 125 V			100 mA-3.15 A	
						AC 125 V		25CT		25
				Surface mount type		DC 125 V	Inrush-withstand	2001	Over 3.15 A-5 A	20
						DC 86 V			100 mA-5 A	
	•	•				DC 86 V	-	DC86V11CT	100 mA-8 A	20
		•				DC 00 V		11CF	100 mA-10 A	19
	•	•			w1.6 × <sup>H</sup> 1.05 × <sup>L</sup> 3.2		Quick-acting	11CFB	100 mA-10 A	18
					1.0 ~ 1.03 ~ 3.2	DC 72 V		11CT	100 mA-10 A	19
							Inrush-withstand	11CTB	100 mA-10 A	18
						AC 32 V		ПСТВ	100 IIIA-10 A	10
						DC 72 V			28 mA-250 mA	
						AC 25 V				1
	•	•			<sup>w</sup> 1.5 × <sup>н</sup> 1.2 × <sup>∟</sup> 2.4	DC 32 V		MCF3	260 mA-1 A	31
						AC 12.5 V	Quick-acting			
						DC 25 V			1.1 A-2.5 A	
						AC 250 V				
	•	•		Code and in the code		DC 125 V		25RF	100 mA-10 A	28
				Sub-miniature type with leads	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 9	AC 125 V				
	•	•				DC 125 V		25RT	100 mA-5 A	28
	•	•				DO 123 V		KST2	1 A-30 A	70
	•				<sup>φ</sup> 10.3 × <sup>∟</sup> 38.1	AC 250 V		SKM10	100 mA-30 A	90
	•	•			10.5 * 30.1	DC 500 V	 Inrush-withstand		1 A–10 A	42
	•					AC 500 V	III usii-wiliislaiiu	SHV4	1 A-10 A	37
						AC 400 V	-	OTTV4	I A-IUA	31
	•	•				DC 400 V		SHV14	1 A–20 A	40
	•	•		Cartridge type		AC 380 V		SHV4	Over 10 A-20 A	37
	•	•			<sup>¢</sup> 6.35 × <sup>∟</sup> 31.8		Named ti	SS2	50 mA-5 A	94
	•	•				40.0501	Normal-acting	SS6	Over 5 A–8 A	95
	•	•				AC 250 V		CES14	100 mA-10 A	67
	•	•					Inrush-withstand	ST4	100 mA-30 A	99
	•	•				AC 125 V	Normal-acting	SS6	Over 8 A–15 A	95

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

PS *	<b>₽</b> 5 <b>₽</b>	Or OF	(\$)	\$ Shape	Dimensions (mm)	Rated voltage	Characteristic	Type name	Rated current	Page
	•	•				AC 125 V		CES6	100 mA-15 A	65
	•	•			φ c 25 \24 0	AC 125 V	Inrush-withstand	ST6	100 mA-30 A	102
	•	•			<sup>¢</sup> 6.35 × <sup>L</sup> 31.8	DC 125 V		ST6 N1	100 mA-15 A	103
	•	•				DC 700 V	Inrush-withstand	SHV16	1 A-4 A	41
	•	•				AC 250 V	N	SL4	80 mA-2 A	91
	•	•			<sup>φ</sup> 6.35 × <sup>∟</sup> 25.4	AC 125 V	Normal-acting	SL2	80 mA-6 A	91
	•	•				DC 500 V	Inrush-withstand	SHV18	1 A-30 A	41
	•	•		Cartridge type		AC 500 V DC 400 V	Inrush-withstand	SHV12	100 mA-6.3 A	39
	•	•		Carringe type		AC 380 V		SHV2	1 A-6.3 A	37
	•	•					Normal-acting	MQ4	62 mA-3 A	74
	•	•			<sup>φ</sup> 5.2 × <sup>L</sup> 20	AC 250 V	Inrush-withstand	MT4	100 mA-3.5 A	80
	•	•					iniusn-wiinstand	MT4 D	100 mA-3.5 A	82
	•	•				AC 125 V	Normal-acting	MQ2	62 mA-10 A	72
	•	•				AC 125 V	Inrush-withstand	ULTSC	100 mA-10 A	108
	•	•				DC 450 V	Initusti-withstand	SHV20	500 mA-6.3 A	42
	•	•			<sup>φ</sup> 4.6 × <sup>L</sup> 14	AC 125 V	Normal-acting	SQ8	80 mA-3 A	92
	•	•			4.0 ^ 14	AC 123 V	Inrush-withstand	MT8	100 mA-3 A	85
	•	•			<sup>φ</sup> 10.3 × <sup>L</sup> 38.1	AC 250 V	Inrush-withstand	SKM7	100 mA-30 A	89
	•	•				AC 500 V	IIIIusii-wiliistaiiu	SHV33	10 A-30 A	43
	•	•					Normal-acting	SS1	50 mA-5 A	93
	•	•				AC 250 V	Normal-acting	SS5	Over 5 A–8 A	95
	•	•				AC 230 V	Inrush-withstand	CES15	100 mA-30 A	68
	•	•			<sup>¢</sup> 6.35 × <sup>∟</sup> 31.8		IIII usii-wiliistaiiu	ST3	100 mA-30 A	98
	•	•			0.55 ^ 51.6		Normal-acting	SS5	Over 8 A–15 A	95
	•	•			A	AC 125 V		CES7	100 mA-15 A	66
							Inrush-withstand	ST5	100 mA-30 A	100
						AC 125 V	IIII usi i-witi istailu	313	Over 8 A-30 A	100
	•	•				DC 125 V		ST5 N1	Over 8 A–15 A	101
	•	•		Cartridge type-	<sup>φ</sup> 6.35 × <sup>L</sup> 30	DC 125 V		DC125VTLKR	800 mA-35 A	64
				with leads	<sup>φ</sup> 6.35 × <sup>L</sup> 25.4	DC 450 V		SHV27	6.3 A	43
					J.JJ 2J. <del>4</del>	DC 420 V	Inrush-withstand	511421	8 A–30 A	40
						AC 400 V	แแนรแ-พเเมรเสกิด	SHV11	100 mA-6.3 A	38
						DC 400 V		OTTV TT	100 IIIA-0.3 A	36
	•	•				AC 380 V		SHV1	1 A-6.3 A	36
	•	•			<sup>φ</sup> 5.2 × <sup>L</sup> 20		Normal-acting	MQ3	62 mA-3 A	73
	•	•			0.2 ^ 20	AC 250 V	Inrush-withstand	MT3	100 mA-3.5 A	75
	•	•					แแนรแ-พเนเรเสทีน	MT3 D	100 mA-3.5 A	77
	•	•					Normal-acting	MQ1	62 mA-10 A	71
	•	•				AC 125 V	Inrush-withstand	ULTSCR	100 mA-10 A	109
	•	•			<sup>φ</sup> 4.6 × <sup>∟</sup> 14	AU 120 V	Normal-acting	SQ7	80 mA-3 A	92
	•	•			17		Inrush-withstand	MT7	100 mA-3 A	85

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

PS *	(l) or <b>91</b>	OF OF	(2)	\$ Shape	Dimensions (mm)	Rated voltage	Characteristic	Type name	Rated current	Page
	•	•				AC 250 V	Quick-acting	NQ3	62 mA-10 A	87
	•	•		Cartridge type	<sup>¢</sup> 4 × <sup>∟</sup> 9	AC 250 V	Inrush-withstand	NT3	100 mA-10 A	88
	•	•		with leads	4 × 9	AC 125 V	Quick-acting	NQ1	62 mA-10 A	87
	•	•				AC 125 V	Inrush-withstand	NT1	100 mA-10 A	88
	•	•		Bolted connection type	<sup>¢</sup> 10 × <sup>∟</sup> 32	AC 500 V	_	500VBL1030A	5 A-50 A	54
	•	•		Board mount type	<sup>¢</sup> 10 × <sup>∟</sup> 31	DC 500 V		500VBI1030	5 A–50 A	54
	•	•	•		<sup>w</sup> 1.6 × <sup>H</sup> 1.05 × <sup>L</sup> 3.2	DC 32 V	Inrush-withstand	32V11CF	800 mA-6.3 A	21
•				Surface mount type	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	AC 125 V	Quick-acting	25CF	63 mA-6.3 A	24
•				196-	2.57 × 2.57 × 0.1	AC 125 V	Inrush-withstand	25CT	100 mA-5 A	25
•				Sub-miniature type with leads	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 9	AC 125 V	Quick-acting	25RF	100 mA-5 A	28
•						AC 250 V	Normal-acting	250V (A) LLC	500 mA-30 A	124
•					<sup>∮</sup> 10.3 × <sup>∟</sup> 38.1	AC 250 V	Inrush-withstand	250V A TLLC	500 mA-30 A	129
•					10.3 × 38.1	A C 405 \/	Normal-acting	(A) LLC	500 mA-30 A	114
•						AC 125 V		A TLLC	500 mA-30 A	119
•						AC 300 V	Inrush-withstand	SHV4	1 A-20 A	37
•							Normal-acting	250V (A) LNC	100 mA-20 A	123
•					<sup>φ</sup> 6.35 × <sup>∟</sup> 31.8	AC 250 V	Inrush-withstand	250V A TLNC	100 mA-20 A	128
•						10.1051/	Normal-acting	(A) LNC	100 mA-20 A	113
•						AC 125 V	Inrush-withstand	(A) TLNC	100 mA-20 A	118
•							Normal-acting	250V (A) LC	100 mA-20 A	122
•					d I	AC 250 V	Inrush-withstand	250V (A) TLC	100 mA-30 A	127
•				Cartridge type	<sup>6</sup> 6.35 × <sup>1</sup> 30		Normal-acting	(A) LC	100 mA-20 A	112
•						AC 125 V	Inrush-withstand	(A) TLC	100 mA-30 A	117
•						AC 300 V	Inrush-withstand	SHV2	1 A-6.3 A	37
•							Normal-acting	250V (A) SC	100 mA-10 A	121
•					<sup>φ</sup> 5.2 × <sup>L</sup> 20	AC 250 V	Inrush-withstand	250V A TSC	100 mA-10 A	126
•							Normal-acting	(A) SC	100 mA-10 A	111
•						AC 125 V	Inrush-withstand	(A) TSC	100 mA-10 A	116
•							Normal-acting	250V A MSC	100 mA-5 A	120
•					d 1	AC 250 V	Inrush-withstand	250V A TMSC	100 mA-5 A	125
•					<sup>¢</sup> 4.6 × <sup>L</sup> 16	_	Normal-acting	(A) MSC	100 mA-5 A	110
•						AC 125 V	Inrush-withstand	_	100 mA-5 A	115
•							Normal-acting	250V A LLCR	500 mA-30 A	124
•					d !	AC 250 V		250V A TLLCR	500 mA-30 A	129
•					<sup>¢</sup> 10.3 × <sup>∟</sup> 38.1		Normal-acting	(A) LLCR	500 mA-30 A	114
•						AC 125 V	Inrush-withstand		500 mA-30 A	119
•						<b>—</b>	Normal-acting	250V A LNCR	100 mA-20 A	123
•				Cartridge type	d !	AC 250 V		250V A TLNCR	100 mA-20 A	128
•				with leads	<sup>¢</sup> 6.35 × <sup>L</sup> 31.8		Normal-acting	(A) LNCR	100 mA-20 A	113
•						AC 125 V	Inrush-withstand		100 mA-20 A	118
•							Normal-acting	250V @ LCR	100 mA-20 A	122
•					d = 0 = 1 = -	AC 250 V	Inrush-withstand		100 mA-30 A	127
•					<sup>¢</sup> 6.35 × <sup>L</sup> 30		Normal-acting	(A) LCR	100 mA-20 A	112
•						AC 125 V	Inrush-withstand		100 mA-30 A	117

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

PS *	(I) or <b>71</b>	or Of	(3)	\$ Shape	Dimensions (mm)	Rated voltage	Characteristic	Type name	Rated current	Page
•						AC 300 V	Inrush-withstand	SHV1	1 A-6.3 A	36
•						AC 250 V	Normal-acting	250V (A) SCR	100 mA-10 A	121
•					<sup><i>ϕ</i></sup> 5.2 × <sup>∟</sup> 20	AC 250 V	Inrush-withstand	250V A TSCR	100 mA-10 A	126
•						AC 125 V	Normal-acting	A SCR	100 mA-10 A	111
•				Cartridge type with leads		AC 125 V	Inrush-withstand	A TSCR	100 mA-10 A	116
•						A C 250 V	Normal-acting	250V A MSCR	100 mA-5 A	120
•					<sup>φ</sup> 4.6 × <sup>L</sup> 16	AC 250 V	Inrush-withstand	250V A TMSCR	100 mA-5 A	125
•					4.0 × 10	AC 125 V	Normal-acting	A MSCR	100 mA-5 A	110
•						AC 125 V	Inrush-withstand	A TMSCR	100 mA-5 A	115
	•			Surface mount	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1	DC 72 V	Quick-acting	25CF	18 A	24
	•			type	<sup>w</sup> 1.6 × <sup>H</sup> 1.05 × <sup>L</sup> 3.2	DC 35 V	Inrush-withstand	DC35V11CT	100 mA-10 A	20
	•				<sup>φ</sup> 10.3 × <sup>L</sup> 38.1	AC 125 V		SKM2	3 A-15 A	89
	•				<sup>φ</sup> 6.35 × <sup>L</sup> 31.8	AC 250 V	Inrush-withstand	CES14	Over 10 A-15 A	67
	•				0.30 × 31.0	AC 125 V		CES6	Over 15 A-20 A	65
	•				<sup>φ</sup> 6.35 × <sup>∟</sup> 15.9	AC 125 V		SU2	100 mA-20 A	104
	•				0.35 × 15.9	DC 60 V	Normal-acting	DCSU2	Over 5 A-20 A	105
	•			Cartridge type				MQ4	Over 3 A-15 A	74
	•					AC 250 V		MT4	Over 3.5 A-15 A	80
					<sup>φ</sup> 5.2 × <sup>∟</sup> 20			MT4 D	Over 3.5 A–15 A	82
					5.2 ^ 20		Inrush-withstand	WI14 D	100 mA-15 A	02
	•					DC 125 V		MT4 N1D	100 mA-3.5 A	83
	•							MT4 N2D	Over 3.5 A-15 A	84
	•				<sup>φ</sup> 6.35 × <sup>L</sup> 15.9	AC 125 V	Normal acting	SU1	80 mA–5 A	104
	•						Normal-acting	MQ3	Over 3 A–15 A	73
	•					AC 250 V		MT3	Over 3.5 A-15 A	75
				Cartridge type with leads	<sup>φ</sup> 5.2 × <sup>L</sup> 20			MT3 D	Over 3.5 A-15 A	77
					3.2 ^ 20		Inrush-withstand	WITS D	100 mA-15 A	] ' '
						DC 125 V		MT3 N1D	100 mA-3.5 A	78
	•							MT3 N2D	Over 3.5 A–15 A	79
		•		Cartridge type	d I			MQ2	Over 10 A-15 A	72
		•		Cartridge type with leads	<sup>¢</sup> 5.2 × <sup>∟</sup> 20	AC 125 V	Normal-acting	MQ1	Over 10 A-15 A	71
			•	Surface mount type	<sup>W</sup> 1.6 × <sup>H</sup> 1.05 × <sup>L</sup> 3.2	AC 32 V DC 32 V	Inrush-withstand	32V11CF	800 mA-6.3 A	21
			•	Sub-miniature type with leads	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 9	AC 125 V DC 125 V	Quick-acting	25RF	200 mA-5 A	28

<sup>\*</sup> Fuses with rated currents of less than 1 A are not considered electrical products per the Electrical Appliance and Material Safety Law.

or or or <b>(2)</b>	\$ Shape	Dimensions (mm)	Rated voltage	Characteristic	Type name	Rated current	Page
				Quick-acting	P25CF	63 mA-18 A	26
		Wo Ho Io (	DC 60 V	Inrush-withstand	P25CT	100 mA-5 A	26
		<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 6.1		Quick-acting	DC35VP25CF	63 mA-18 A	27
	Surface mount		DC 35 V	Inrush-withstand	DC35VP25CT	100 mA-5 A	27
	type			Quick-acting	P11CF	100 mA-10 A	22
		W H	DC 72 V	Inrush-withstand	P11CT	100 mA-10 A	22
		<sup>™</sup> 1.6 × <sup>H</sup> 1.05 × <sup>L</sup> 3.2	DO 05 1/	Quick-acting	DC35VP11CF	100 mA-10 A	23
			DC 35 V	Inrush-withstand	DC35VP11CT	100 mA-10 A	23
			AC 90 V DC 90 V	Quick-acting	P25RF	100 mA-10 A	29
	Sub-miniature type with leads	<sup>w</sup> 2.57 × <sup>H</sup> 2.57 × <sup>L</sup> 9	AC 90 V DC 60 V	Inrush-withstand	P25RT	100 mA-6.3 A	29
			DC 35 V	Quick-acting	DC35VP25RF	100 mA-10 A	30
			DC 35 V	Inrush-withstand	DC35VP25RT	100 mA-6.3 A	30
		<sup>¢</sup> 6.35 × <sup>∟</sup> 31.8	DC 500 V		NSHV14	10 A	46
	Cartridge type	<sup>∮</sup> 5.2 × <sup>∟</sup> 20	AC 42 V DC 42 V	Inrush-withstand	PMT4	100 mA-20 A	86
			DC 450 V		NSHV12	100 mA-6.3 A	45
		<sup>¢</sup> 10.3 × <sup>∟</sup> 38.1	DC 600 V	Normal-acting	LLD6500	15 A	105
			AC 500 V		NSHV3	1 A-10 A	44
		<sup> </sup> 6.35 × <sup>∟</sup> 31.8	AC 400 V		NSHV13	5 A-25 A	44
	Cartridge type with leads	0.55 ^ 51.6	DC 400 V	Inrush-withstand	NSHV23A	1 A-20 A	47
			DC 700 V	Initusti-withstand	NSHV15	1 A-4 A	46
		<sup>φ</sup> 6.35 × <sup>L</sup> 25.4	DC 500 V		NSHV17	1 A-30 A	47
		<sup>φ</sup> 4 × <sup>L</sup> 9	DC 100 V		PNT5	100 mA-10 A	86
		<sup>φ</sup> 40 × <sup>L</sup> 65	DC 800 V DC 500 V		PT4065	400 A–500 A	56
		<sup>φ</sup> 31 × <sup>L</sup> 51			DC450VPT3050	250 A-350 A	49
		<sup>φ</sup> 30 × <sup>L</sup> 50	DC 450 V		DC450VBT3050	250 A-350 A	56
		<sup>φ</sup> 26 × <sup>L</sup> 46		_	DC450VPT2545	180 A–225 A	48
		<sup>φ</sup> 25 × <sup>L</sup> 42.6	DC 500 V		DC500VBT2543	225 A	55
	Bolted connection type	<sup>¢</sup> 20 × <sup>∟</sup> 35	DC 450 V		DC450VPT2035	100 A-150 A	48
			AC 450 V	_	AC450VBL1030C	60 A	52
		<sup>¢</sup> 10 × <sup>∟</sup> 32	DC 500 V		500VBL1030A	5 A-40 A	54
				_	DC500VBL1030F	60 A	53
			DC 72 V	_	DC72VBL1030	50 A-70 A	53
		<sup>¢</sup> 6.35 × <sup>L</sup> 31.8	DC 500 V		DC500VBC635C	5 A-30 A	51
		<sup>⋄</sup> 6.35 × <sup>L</sup> 24.6			DC500VBC625A	5 A-35 A	49
		<sup>∅</sup> 10 × <sup>L</sup> 31	DC 500 V	_	500VBI1030	5 A-40 A	54
	Board mount		DC 600 V	_	DC600VBI625C	30 A	51
	type	<sup>\$\phi\$</sup> 6.35 × \(^{\text{24.6}}\)	DC 550 V DC 300 V		DC550VBI625C	35 A	50
			DC 500 V		DC500VBI625C	5 A-35 A	50

# Search by type name

A TLNCR  A TMSC  A TMSCR  A TSC  A TSCR  C CES14  CES14 N1  CES14 N2  CES15  CES15 N1  CES6  CES6 N1  CES7  CES7 N1  CES7  CES7 N1  DC125VTLKR  DC300V25CF  DC35VP1CT  DC35VP11CT  DC35VP25CF  DC35VP25CT  DC35VP25RT  DC450VBT3050  DC450VPT2035	115 115 116 116 116 67 68 68 69 65 65 66 66 25 20 23 23 27 27 30 30 56	N N N N N N N N N N N N N N N N N N N	MCF3 MQ1 MQ1 MQ1 MQ2 MQ2 MQ2 MQ3 MQ3 MQ3 MQ3 MQ4 MQ4 MQ4 M1 MT3 MT3 MT3 MT3 MT3 MT3 MT3 MT3 MT3 MT4	31 71 72 72 73 73 74 74 75 77 75 78 76 79 80 82 80 83 81 84	S	SHV2 SHV20 SHV27 SHV33 SHV4 SKM10 SKM10 N1 SKM2 SKM7 SL2 SL4 SMC N4 SQ7 SQ8 SS1 SS1 N1	37 42 43 43 37 90 90 89 91 91 35 92 92
A TMSCR A TSC A TSCR CES14 CES14 N1 CES14 N2 CES15 CES15 N1 CES6 CES6 N1 CES7 CES7 N1  DC125VTLKR DC300V25CF DC35V11CT DC35VP11CT DC35VP25CF DC35VP25CF DC35VP25RF DC35VP25RT DC450VBT3050	115 116 116 116 67 68 68 69 65 65 66 66 25 20 23 23 27 27 30 30	N N N N N N N N N N N N N N N N N N N	MQ1 N1 MQ2 MQ2 N1 MQ3 MQ3 N1 MQ4 MQ4 N1 MT3 N1 MT3 N1 MT3 N1 MT3 N2 MT3 N2 MT3 N2 MT4 N1 MT4 N1 MT4 N1 MT4 N1 MT4 N2 MT4 N2 MT4 N2D	71 72 72 73 73 74 74 75 77 75 78 76 79 80 82 80 83 81		SHV22 SHV27 SHV33 SHV4 SKM10 SKM10 N1 SKM2 SKM7 SL2 SL4 SMC N4 SQ7 SQ8 SS1	42 43 43 37 90 90 89 89 91 91 35 92 92
A TSC	116 116 67 68 68 69 65 65 66 66 25 20 23 23 27 27 30 30	N N N N N N N N N N N N N N N N N N N	MQ2 MQ2 N1 MQ3 MQ3 N1 MQ4 MQ4 N1 MT3 MT3 D MT3 N1 MT3 N1D MT3 N2 MT3 N2 MT4 N2 MT4 N1 MT4 N1 MT4 N1 MT4 N2 MT4 N2 MT4 N2	72 73 73 74 74 75 77 75 78 76 79 80 82 80 83 81		SHV27 SHV33 SHV4 SKM10 SKM10 N1 SKM2 SKM7 SL2 SL4 SMC N4 SQ7 SQ8 SS1	43 43 37 90 90 89 91 91 35 92 92
A TSCR  CES14 CES14 N1 CES14 N2 CES15 CES15 CES15 N1 CES6 CES6 N1 CES7 CES7 N1  DC125VTLKR DC300V25CF DC35V11CT DC35VP11CF DC35VP11CT DC35VP25CF DC35VP25CF DC35VP25RF DC35VP25RF DC35VP25RT DC450VBT3050	116 67 68 68 69 65 65 66 66 25 20 23 23 27 27 30 30	N N N N N N N N N N N N N N N N N N N	MQ2 N1 MQ3 MQ3 N1 MQ4 MQ4 N1 MT3 MT3 D MT3 N1 MT3 N1D MT3 N2 MT3 N2 MT4 N2 MT4 N1 MT4 N1 MT4 N1 MT4 N2 MT4 N2 MT4 N2D	72 73 73 74 74 75 77 75 78 76 79 80 82 80 83 81		SHV33 SHV4 SKM10 SKM10 N1 SKM2 SKM7 SL2 SL4 SMC N4 SQ7 SQ8 SS1	43 37 90 90 89 89 91 91 35 92 92
C CES14 CES14 N1 CES14 N2 CES15 CES15 CES15 N1 CES6 CES6 N1 CES7 CES7 N1  DC125VTLKR DC300V25CF DC35V11CT DC35VP11CT DC35VP25CF DC35VP25CF DC35VP25RF DC35VP25RF DC35VP25RT DC450VBT3050	67 68 68 69 65 65 66 66 25 20 23 23 27 27 30 30	N N N N N N N N N N N N N N N N N N N	MQ3 MQ3 N1 MQ4 MQ4 N1 MT3 MT3 D MT3 N1 MT3 N1D MT3 N2 MT3 N2 MT4 N2 MT4 N1 MT4 N1 MT4 N2 MT4 N2 MT4 N2	73 73 74 74 75 77 75 78 76 79 80 82 80 83 81		SHV4 SKM10 SKM10 N1 SKM2 SKM7 SL2 SL4 SMC N4 SQ7 SQ8 SS1	37 90 90 89 89 91 91 35 92 92
CES14 N1 CES14 N2 CES15 CES15 N1 CES6 CES6 N1 CES7 CES7 N1  DC125VTLKR DC300V25CF DC35V11CT DC35VP11CT DC35VP25CF DC35VP25CF DC35VP25CF DC35VP25RF DC35VP25RT DC450VBT3050	67 68 68 69 65 66 66 64 25 20 23 23 27 27 30 30	N N N N N N N N N N N N N N N N N N N	MQ3 N1 MQ4 MQ4 N1 MT3 MT3 D MT3 N1 MT3 N1D MT3 N2 MT3 N2 MT4 N2 MT4 N1 MT4 N1D MT4 N2 MT4 N2 MT4 N2D	73 74 74 75 77 75 78 76 79 80 82 80 83 81		SKM10 SKM10 N1 SKM2 SKM7 SL2 SL4 SMC N4 SQ7 SQ8 SS1	90 90 89 89 91 91 35 92 92
CES14 N1 CES14 N2 CES15 CES15 N1 CES6 CES6 N1 CES7 CES7 N1  DC125VTLKR DC300V25CF DC35V11CT DC35VP11CT DC35VP25CF DC35VP25CF DC35VP25CF DC35VP25RF DC35VP25RT DC450VBT3050	67 68 68 69 65 66 66 64 25 20 23 23 27 27 30 30	N N N N N N N N N N N N N N N N N N N	MQ4 MQ4 N1 MT3 MT3 D MT3 N1 MT3 N1D MT3 N2 MT3 N2 MT3 N2D MT4 MT4 N1D MT4 N1D MT4 N1D MT4 N2 MT4 N2D	74 74 75 77 75 78 76 79 80 82 80 83 83		SKM10 N1 SKM2 SKM7 SL2 SL4 SMC N4 SQ7 SQ8 SS1	90 89 89 91 91 35 92 92
CES14 N2 CES15 CES15 N1 CES6 CES6 N1 CES7 CES7 N1  DC125VTLKR DC300V25CF DC35V11CT DC35VP11CT DC35VP25CF DC35VP25CF DC35VP25RF DC35VP25RF DC35VP25RT DC450VBT3050	68 68 69 65 66 66 64 25 20 23 23 27 27 30 30		MQ4 N1 MT3 MT3 D MT3 N1 MT3 N1D MT3 N2 MT3 N2D MT4 N4 MT4 D MT4 N1 MT4 N1D MT4 N2 MT4 N2D	74 75 77 75 78 76 79 80 82 80 83 81		SKM2 SKM7 SL2 SL4 SMC N4 SQ7 SQ8 SS1	89 89 91 91 35 92 92
CES15 CES15 N1 CES6 CES6 N1 CES7 CES7 N1  DC125VTLKR DC300V25CF DC35V11CT DC35VP11CF DC35VP11CT DC35VP25CF DC35VP25CF DC35VP25RF DC35VP25RF DC35VP25RT DC450VBT3050	68 69 65 66 66 64 25 20 23 23 27 27 30 30		MT3 D MT3 N1 MT3 N1D MT3 N2 MT3 N2D MT4 N4 MT4 D MT4 N1 MT4 N1D MT4 N2 MT4 N2D	75 77 75 78 76 79 80 82 80 83		SKM7 SL2 SL4 SMC N4 SQ7 SQ8 SS1	89 91 91 35 92 92
CES15 N1 CES6 CES6 N1 CES7 CES7 N1  DC125VTLKR DC300V25CF DC35V11CT DC35VP11CF DC35VP25CF DC35VP25CF DC35VP25CF DC35VP25RF DC35VP25RF DC35VP25RT DC450VBT3050	69 65 65 66 66 64 25 20 23 23 27 27 27		MT3 D MT3 N1 MT3 N1D MT3 N2 MT3 N2D MT4 MT4 D MT4 N1 MT4 N1D MT4 N2 MT4 N2	77 75 78 76 79 80 82 80 83		SL2 SL4 SMC N4 SQ7 SQ8 SS1	91 91 35 92 92 93
CES6 CES6 N1 CES7 CES7 N1  DC125VTLKR DC300V25CF DC35V11CT DC35VP11CF DC35VP25CF DC35VP25CF DC35VP25CF DC35VP25RF DC35VP25RF DC35VP25RT DC450VBT3050	65 66 66 64 25 20 23 23 27 27 30 30	N N N N N N	MT3 N1 MT3 N1D MT3 N2 MT3 N2D MT4 MT4 D MT4 N1 MT4 N1D MT4 N2 MT4 N2D	75 78 76 79 80 82 80 83		SL4 SMC N4 SQ7 SQ8 SS1	91 35 92 92 93
CES6 N1 CES7 CES7 N1  DC125VTLKR DC300V25CF DC35V11CT DC35VP11CF DC35VP25CF DC35VP25CF DC35VP25CF DC35VP25RF DC35VP25RF DC35VP25RT DC450VBT3050	65 66 66 64 25 20 23 23 27 27 27 30 30	N N N N N N	MT3 N1D MT3 N2 MT3 N2D MT4 MT4 D MT4 N1 MT4 N1D MT4 N2 MT4 N2D	78 76 79 80 82 80 83 81		SMC N4 SQ7 SQ8 SS1	35 92 92 93
CES7 CES7 N1  DC125VTLKR DC300V25CF DC35V11CT DC35VP11CF DC35VP25CF DC35VP25CF DC35VP25CT DC35VP25RF DC35VP25RT DC450VBT3050	66 66 64 25 20 23 23 27 27 27 30 30	N N N N N	MT3 N2 MT3 N2D MT4 MT4 D MT4 N1 MT4 N1D MT4 N2 MT4 N2D	76 79 80 82 80 83	-	SQ7 SQ8 SS1	92 92 93
DC125VTLKR DC300V25CF DC35V11CT DC35VP11CF DC35VP25CF DC35VP25CF DC35VP25CF DC35VP25RF DC35VP25RT DC450VBT3050	66 64 25 20 23 23 27 27 27 30	N N N N N	MT3 N2D MT4 MT4 D MT4 N1 MT4 N1D MT4 N2 MT4 N2D	79 80 82 80 83 81	_	SQ8 SS1	92 93
DC125VTLKR DC300V25CF DC35V11CT DC35VP11CF DC35VP25CF DC35VP25CF DC35VP25CT DC35VP25RF DC35VP25RF DC35VP25RT DC450VBT3050	64 25 20 23 23 27 27 27 30 30	N N N N	MT4 MT4 D MT4 N1 MT4 N1D MT4 N2 MT4 N2D	80 82 80 83 81	-	SS1	93
DC300V25CF DC35V11CT DC35VP11CF DC35VP11CT DC35VP25CF DC35VP25CT DC35VP25RF DC35VP25RF DC35VP25RT DC450VBT3050	25 20 23 23 27 27 27 30 30	N N N	MT4 D MT4 N1 MT4 N1D MT4 N2 MT4 N2D	82 80 83 81			
DC300V25CF DC35V11CT DC35VP11CF DC35VP11CT DC35VP25CF DC35VP25CT DC35VP25RF DC35VP25RF DC35VP25RT DC450VBT3050	25 20 23 23 27 27 27 30 30	N N N	MT4 N1 MT4 N1D MT4 N2 MT4 N2D	80 83 81		CC1 N11	000
DC35V11CT DC35VP11CF DC35VP11CT DC35VP25CF DC35VP25CT DC35VP25RF DC35VP25RT DC450VBT3050	20 23 23 27 27 27 30 30	N N N	MT4 N1D MT4 N2 MT4 N2D	83 81		DOLINI	93
DC35VP11CF DC35VP11CT DC35VP25CF DC35VP25CT DC35VP25RF DC35VP25RF DC35VP25RT DC450VBT3050	23 23 27 27 27 30 30	N N	MT4 N2 MT4 N2D	81	1	SS2	94
DC35VP11CT DC35VP25CF DC35VP25CT DC35VP25RF DC35VP25RT DC450VBT3050	23 27 27 30 30	N	MT4 N2D		1	SS2 N1	94
DC35VP25CF DC35VP25CT DC35VP25RF DC35VP25RT DC450VBT3050	27 27 30 30	N		84	1	SS5	95
DC35VP25CT DC35VP25RF DC35VP25RT DC450VBT3050	27 30 30				1	SS5 N1	96
DC35VP25RF DC35VP25RT DC450VBT3050	30 30	N	MT7	85		SS6	95
DC35VP25RF DC35VP25RT DC450VBT3050	30 30		MT8	85	1	SS6 N1	97
DC35VP25RT DC450VBT3050	30				J	ST3	98
DC450VBT3050						ST3 N1	98
		NI	NQ1	87	]	ST4	99
ロルスコロソピエフロスケ	48		NQ3	87	1	ST4 N1	99
DC450VPT2545	48		NSHV12	45	1	ST5	10
DC450VPT3050	49		NSHV13	44	1	ST5 N1	10
DC500VBC625A	49		NSHV14	46	-	ST6	10
DC500VBC635C	51		NSHV15	46	-	ST6 N1	10:
DC500VBI625C	50		NSHV17	47	-	SU1	10
					-	SU2	
DC500VBL1030F	53		NSHV23A	47	-	302	10
DC500VBT2543	55		NSHV3	44	-		
DC550VBI625C	50		NT1	88	_	TI 0 NI4	10
DC600VBI625C	51	l L	NT3	88	J I	TLC N4	100
DC72VBL1030	53					TLCR N4	10
DC86V11CT	20				1		
DCSU2	105	· -	P11CF	22	U	ULTSC	10
		_	P11CT	22		ULTSC N1	10
		. –	P25CF	26		ULTSCR	10
EQ	57		P25CT	26		ULTSCR N1	10
ET	58	F	P25RF	29			
ET6	59	F	P25RT	29			
ET6R	60	F	PMT4	86			
		F	PNT5	86		Fuseholders / Fus	e clips
		F	PT4065	56		BM-LQ-I-13	13
LIONIZ	61	_			-	BM-LQ-I-15	13
I HQ N/	62					BM-SS-I-14	13
	63	SS	SHV1	36	]		13
HT N5		_			1		13
		. –			1		13
HT N5 HTR N5	70			_	1		13
HT N5 HTR N5	70		OIIVI <del>T</del>		1		
HT N5 HTR N5	70 70	5	SH\/16	11	1	H-0048-2	13
	ET6 ET6R HQ N7 HT N5	ET6 59 ET6R 60 H HQ N7 61 HT N5 62 HTR N5 63	ET6 59 ET6R 60 I I I I I I I I I I I I I I I I I I	ET6 59 ET6R 60  P25RT PMT4 PNT5 PT4065  H HQ N7 61 HT N5 62 HTR N5 63  KST2 70 KST2 N1 70  P25RT PMT4 PNT5 PX4065  SHV14	ET6 59 ET6R 60  P25RT 29 PMT4 86 PNT5 86 PT4065 56  H HQ N7 61 HT N5 62 HTR N5 63 S SHV1 36 SHV11 38 SHV11 38 SHV11 38 SHV11 38	ET6 59 ET6R 60  P25RT 29 PMT4 86 PNT5 86 PT4065 56  H Q N7 61 HT N5 62 HTR N5 63 SHV1 36 SHV11 38 SHV11 38 SHV11 38 SHV12 39 KST2 N1 70 SHV14 40	ET6 59 ET6R 60  PMT4 86 PNT5 86 PT4065 56  H Q N7 61 HT N5 62 HTR N5 63 S SHV1 36 SHV11 38 SHV11 38 SHV11 38 KST2 70 KST2 N1 70  P25RT 29 PMT4 86 PNT5 86 PT4065 56  Fuseholders / Fus BM-LQ-I-13 BM-LQ-I-15 BM-SS-I-14 H-0014-2 H-0016-2 H-0017-2 H-0017-2 H-0032-2

## Safety Precautions

## **↑** WARNING

Failure to properly select, install, and use fuses may result not only in property damage due to fire and other disasters, but also bodily harm, serious injury, and/or death. This catalog contains as references only a portion of the data available for the products listed. Before selecting a fuse, confirm the latest product specifications and parameters with one of SOC's local sales representatives.

- Use fuses within their specified limits. Use outside of specified conditions can cause nuisance operations and disconnection of the fuse-element, among other things, and may lead to the occurrence of accidents. Please note that breaking conditions for currents below the minimum breaking current and which exceed the rated breaking current are outside the range of the specification conditions. Please use this product after ensuring that the actual breaking conditions in the application are not included in this range.
- Product specification will depend on the product type. Please confirm this with your sales representative.
- Before final fuse selection, always test the proposed fuse in your actual equipment to ensure the fuse satisfies all operational and safety requirements.
- Be aware the breaking ability of a fuse will differ depending on whether the circuit is an AC or DC circuit. Fuses intended for use in AC circuits should not be employed in DC circuits, and vice versa, as this may result in accidents such as explosions, property damage, and/or serious injury. (Refer to p. 139 of this catalog.)
- In regard to environmental conditions, represented by the following, use outside of specifications may cause changes to a fuse's electrical characteristics, nuisance operations, and disconnection of the fuse-element, among other things. Please confirm specifications with your SOC sales representative.
  - \* Ambient temperature and/or temperature changes
  - \* High-temperature and/or high-humidity
  - \* Vibrations and/or impacts
  - \* Condensation
- Do not use fuses where they may be exposed to corrosive and/or flammable gasses. Doing so may result in nuisance operations, disconnection of the fuse-element, and/or explosions.
- Do not use ultrasonic cleaning on fuses as this can result in disconnection of the fuse-element, which may lead to an accident.
- Coating or potting a fuse may change its electrical characteristics. Please consult your SOC sales representative before applying treatment as this may result in an accident.
- Never force a fuse into a fuseholder/fuse clip. Contact failure caused by damage to the fuse or deformation of the fuseholder's clips due to impact or forcing the fuse into the holder may significantly alter the fuse's electrical characteristics and lifetime, and may lead to accidents including nuisance operations.
- Turn off all power leading to a fuse before touching it. Failure to do so may result in electrocution or serious burns.
- Products in this catalog are intended for use in standard electronic equipment. Please consult your SOC sales representative before using fuses in life-critical equipment, equipment which requires a high degree of quality and reliability, and any other similar equipment.
- Use sample fuses only for evaluation. Do not reuse sample or other previously used fuses. Properly dispose of fuses in accordance with local laws and regulations.

## IMPORTANT NOTICES

- Operating, electrical, and/or mechanical characteristic limits for products covered in this catalog, as well as product availability, are subject to change without prior notice.
- The content of this catalog was considered to be reliable at the time of its preparation (March 2024); however, the accuracy of information herein cannot be guaranteed. Check with your local SOC sales representative before finalizing fuse selection.
- Questions related to product applications, specifications, or performance characteristics may be directed to SOC sales representatives.

# **SOC Corporation**

Headquarters 3-16-17 Takanawa, Minato-ku, Tokyo 108-0074, Japan

TEL +81-3-5420-1011 FAX +81-3-5420-6699

SOC America Inc. 414 S Service Rd #519, Patchogue, NY 11772 USA

TEL +1-631-472-6666

SOC Asia Pte. Ltd. 15 Jalan Kilang Barat, #07-02 Frontech Centre, Singapore 159357

TEL +65-6376-4115

SOC Europe B.V. Databankweg 1, 3821 AL Amersfoort, the Netherlands

TEL +31-33-450-4000